





**Standard Type 2 Tree Conservation Plan Notes**

1. This plan is submitted to fulfill the woodland conservation requirements for \_\_\_\_\_.
2. If \_\_\_\_\_ expires, then this TCP2 also expires and is no longer valid.
3. Cutting or clearing woodlands not in conformance with this plan or without the expressed written consent of the Planning Director or designee shall be subject to a \$9.00 per square foot mitigation fee.
4. A pre-construction meeting is required prior to the issuance of grading permits. The Department of Public Works and Transportation or the Department of Environmental Resources, as appropriate, shall be contacted prior to the start of any work on the site to conduct a pre-construction meeting where implementation of woodland conservation measures shown on this plan will be discussed in detail.
5. The developer or builder of the lots or parcels shown on this plan shall notify future buyers of any woodland conservation areas through the provision of a copy of this plan at time of contract signing. Future property owners are also subject to this requirement.
6. The property is within ESA 2 formerly the Developing Tier per the 2002 General Plan and in the Developing area per the 2035 General Plan and is zoned R-80.
7. The property is not adjacent to a roadway designated as scenic, historic, a parkway or a scenic byway.
8. The property is not adjacent to a roadway classified as arterial or greater.
9. This plan is/is not grandfathered by CB27-2010, Section 25-119(g).

**Tree Preservation and Retention Notes**

10. All woodlands designated on this plan for preservation are the responsibility of the property owner. The woodland areas shall remain in a natural state. This includes the canopy trees and understory vegetation. A revised tree conservation plan is required prior to clearing woodland areas that are not specifically identified to be cleared on the approved TCP2.
11. Tree and woodland conservation methods such as root pruning shall be conducted as noted on this plan.
12. The location of all temporary tree protection fencing (TPFs) shown on this plan shall be flagged or staked in the field prior to the pre-construction meeting. Upon approval of the locations by the county inspector, installation of the TPFs may begin.
13. All temporary tree protection fencing required by this plan shall be installed prior to commencement of clearing and grading of the site and shall remain in place until the bond is released for the project. Failure to install and maintain temporary or permanent tree protective devices is a violation of this TCP2.
14. Woodland preservation areas shall be posted with signage as shown on the plans at the same time as the temporary TCF installation. These signs must remain in perpetuity.

**Afforestation and Reforestation Notes**

15. All afforestation and reforestation bonds, based on square footage, shall be posted with the county prior to the issuance of any permits. These bonds will be retained as surety until all required activities have been satisfied or the required timeframe for maintenance has passed, whichever is longer.
16. The planting of afforestation or reforestation areas shall be completed within one (1) year of approval of this plan. Seedling planting is to occur from November through May only. No planting shall be done while the ground is frozen. Planting with larger caliper stock or containerized stock may be done at any time provided a detailed maintenance schedule is provided.
17. If planting cannot occur due to planting conditions, the developer or property owner shall install the fencing and signage in accordance with the approved Type 2 Tree Conservation Plan. Planting shall then be accomplished during the next planting season. If planting is delayed beyond the transfer of the property title to the homeowner, the developer or builder shall obtain a signed statement from the purchaser indicating that they understand that the reforestation area is located on their property and that reforestation will occur during the next planting season. A copy of that document shall be presented to the county inspector.
18. Reforestation areas shall not be mowed. The management of competing vegetation around individual trees and the removal of noxious, invasive and non-native vegetation within the reforestation areas is acceptable.
19. All required temporary tree protection fencing shall be installed prior to the clearing and grading of the site and shall remain in place until the permanent tree protection fencing is installed with the required planting. The temporary fencing is not required to be installed if the permanent fencing is installed prior to the clearing and grading of the site. Failure to install and maintain temporary or permanent tree protective fencing is a violation of this TCP2.
20. Afforestation / reforestation areas shall be posted with notification signage, as shown on the plans, at the same time as the permanent protection fencing installation. These signs shall remain in perpetuity.
21. The county inspector shall be notified prior to soil preparation or initiation of any tree planting on this site.
22. At time of issuance of the first permit, the following information shall be submitted to the M-NCPPC Planning Department regarding the contractor responsible for implementation of this plan. Contractor name, business name (if different), address, and phone number.
23. Result of annual survival check for each of the required four years after tree planting shall be reported to the M-NCPPC, Planning Department.
24. Failure to establish the afforestation or reforestation within the prescribed time frame will result in the forfeiture of the reforestation bond and/or a violation of this plan including the associated \$9.00 per square foot penalty unless the county inspector approves a written extension.

**Planting Specification Notes**

25. Quantity: (See Plant Schedule)
26. Type: (See Plant Schedule)
27. Plant Quality Standards: The plants selected shall be healthy and sturdy representative of their species. Seedlings shall have a minimum top growth of 18". The diameter of the root collar (the part of the root just below ground level) shall be at least 3/8". The roots shall be well developed and at least 8" long, no more than twenty-five percent (25%) of the root system (both primary and auxiliary/fibrous roots) shall be present.
  - a. Plants that do not have an abundance of well developed terminal buds on the leaders and branches shall be rejected.
  - b. Plants shall be shipped by the nursery immediately after lifting from the field or removal from the green house, and planted immediately upon receipt by the landscape contractor.
  - c. If the plants cannot be planted immediately after delivery to the reforestation site, they shall be stored in the shade with their root masses protected from direct exposure to sun and wind by the use of straw, peat moss, compost, or other suitable material and shall be maintained through periodic watering, until the time of planting.
28. Plant handling: the quantity of seedlings taken to the field shall not exceed the quantity that can be planted in a day. Seedlings, once removed from the nursery or temporary storage area shall be planted immediately.
29. Timing of Planting: The best time to plant seedlings is while they are dormant, prior to spring budding. The most suitable months for planting are March and April, when the soils is moist, but may be planted from March through November. No planting shall be done while the ground is frozen. Planting shall occur within one growing season of the issuance of grading/building permits and/or reaching the final grades and stabilization of planting areas.
30. Seedling Planting: Tree seedlings shall be hand planted using a dibble bar or sharp-shooter shovel. It is important that the seedling be placed in the hole so that the roots can spread out naturally; they shall not be twisted, balled up or bent. Moist soil should then be packed firmly around the roots. Seedlings should be planted at a depth where their roots lie just below the ground surface. Air pockets should not be left after closing the hold which would allow the roots to dry out. See planting details for further explanation. If the contractor wishes to plant by another method, the preparer of this tree conservation plan must be contacted and give his approval before planting may begin.
31. Spacing: See Plant Schedule and/or Planting Plan for spacing requirements. Also refer to the Planting Layout detail for a description of the general planting theory.

Soil: Upon the completion of all grading operations, a soil test shall be conducted to determine what soil preparation and soil amendments, if any, are necessary to create good tree growing

- conditions. Soil samples shall be taken at a rate that provides on soil sample for each area that appears to have a different soil type (if the entire area appears uniform, then only one sample is necessary), and submitted for testing to a private company. The company of choice shall make recommendations for improving the existing soil. The soil will be tested and recommended for corrections of soil texture, pH, magnesium, phosphorus, potassium, calcium and organic matter.
33. Soil Improvement Measures: the soil shall then be improved according to the recommendations made by the testing company.
34. Fencing and Signage: Final protective fencing shall be placed on the visible and/or development side of planting areas. The final protective fence shall be installed upon completion of planting operations unless it was installed during the initial stages of development. Signs shall be posted per the signage detail on this sheet.
35. Planting method: Consult the Planting Detail(s) shown on this plan.
36. Mulching: Apply two-inch thick layer of woodchip or shredded hardwood mulch (as noted) to each planting site (see detail shown on this plan).
37. Groundcover Establishment: the remaining disturbed area between seedling planting sites shall be seeded and stabilized with white clover seed at the rate of 5 lbs/acre.
38. Mowing: No mowing shall be allowed in any planting area.
39. Survival Check for Bond Release: The seedling planting is to be checked at the end of each year for four years to assure that no less than 75% of the original planted quantity survives. If the minimum number has not been provided the area must be supplemented with additional seedlings to reach the required number at time of planting.
40. Source of Seedlings: state name, address, and phone number of nursery or supplier.

**Four-Year Management Plan for Re/Afforestation Areas**

- Field check re-afforestation area according to the following schedule:
- Year 1: Site preparation and tree planting  
Survival check once annually (September-November) see Note 1  
Watering is needed (2 x month)  
Control of undesirable vegetation as needed (1 x in June and 1 x in September minimum)
- Year 2-3: Reinforcement planting is needed (See Note 2)  
Survival check once annually (September-November)  
Control of undesirable vegetation if needed (1 x in May and 1 x in August minimum)
- Year 4: Reinforcement planting if needed (See Note 2)  
Survival check (September - November)
1. Survival Check: Check planted stock against plant list (or as-built) by walking the site and taking inventory. Plants must show vitality. Submit field data forms (Condition Check Sheets) to owner after each inspection. Remove all dead plants.
  2. Reinforcement Planting: Replace dead or missing plants in sufficient quantity to bring the total number of live plants to at least 75% of the number originally planted. If a particular species suffers unusually high mortality, replace with an alternative plant type.
  3. Miscellaneous: Fertilization or watering during years 1 through 3 will be done on as needed basis. Special return operations or recommendations will be conducted on an as needed basis.
41. The removal of noxious, invasive, and non-native plant species shall be done with the use of hand-held equipment only such as pruners or a chain saw. These plants may be cut near the ground and the material less than two inches diameter may be removed from the area and disposed of appropriately. All material from these noxious, invasive, and non-native plants greater than two (2) inches diameter shall be cut to allow contact with the ground, thus encouraging decomposition.
42. The use of broadcast spraying of herbicides is not permitted. However, the use of herbicides to discourage re-sprouting of invasive, noxious or non-native plants is permitted if done as an application of the chemical directly to the cut stump immediately following cutting of plant tops. The use of any herbicide shall be done in accordance with the label instructions and be applied by a certified pesticide applicator.

**POST DEVELOPMENT NOTES**

- When woodlands and/or specimen, historic or champion trees are to remain:**  
If the developer or builder no longer has an interest in the property and the new owner desires to remove a hazardous tree or portion thereof, the new owner shall obtain a written statement from a Certified Arborist or Licensed Tree Expert identifying the hazardous condition and the proposed corrective measures prior to having the work conducted. After proper documentation has been completed per the handout "Guidance for Prince George's County Property Owners, Preservation of Woodland Conservation Areas", the arborist or tree expert may then remove the tree. The stump shall be cut as close to the ground as possible and left in place. The removal or grinding of the stumps in the woodland conservation area is not permitted.
44. If a tree or portion thereof are in imminent danger of striking a structure, parking area, or other high use areas and may result in personal injury or property damage then the certification is not required and the permittee shall take corrective action immediately. The condition of the area shall be fully documented through photographs prior to corrective action being taken. The photos shall be submitted to the inspector for documentation of the damage.
45. Tree work to be completed within a road right-of-way requires a permit from the Maryland Department of Natural Resources unless the tree removal is shown within the approved limits of disturbance on a TCP2. The work is required to be conducted by a Licensed Tree Expert.
46. The removal of noxious, invasive, and non-native plant species from any woodland preservation area shall be done with the use of hand-held equipment only (pruners or a chain saw). These plants may be cut near the ground and material less than two inches diameter may be removed from the area and disposed of appropriately. All material from these noxious, invasive, and non-native plants greater than two (2) inches diameter shall be cut to allow contact with the ground, thus encouraging decomposition.
47. The use of broadcast spraying of herbicides is not permitted. However, the use of herbicides to discourage re-sprouting of invasive, noxious, or non-native plants is permitted if done as an application of the chemical directly to the cut stump immediately following cutting of plant tops. The use of any herbicide shall be done in accordance with the label instructions.
48. The use of chainsaws is extremely dangerous and should not be conducted with poorly maintained equipment, without safety equipment, or by individuals not trained in the use of this equipment for the pruning and/or cutting of trees.
- Protection of Reforestation and Afforestation Areas by Individual Homeowners**
49. Reforestation fencing and signage shall remain in place in accordance with the approved Type 2 Tree Conservation Plan.
50. Reforestation areas shall not be mowed; however, the management of competing vegetation and removal of noxious, invasive, and non-native vegetation around individual trees is acceptable.

M-NCPPC Prince George's County Planning Department Environmental Planning Section APPROVAL NATURAL RESOURCES INVENTORY	
NRI- -2017	
Approved by	Date
01 Revision	
02 Revision	
03 Revision	

**QUALIFIED PROFESSIONAL CERTIFICATION**

This complies with the current requirements of Subtitle 25 and the Environmental Technical Manual.

Signed: *John P. Markovich* Date: 7/2/2017

John P. Markovich  
JM Forestry Services, LLC  
11552 Timberbrook Drive  
Waldorf, MD 20601  
Phone: 301-645-4977  
E-mail: jpmarkovich@comcast.net

Prince George's County Planning Department, M-NCPPC Environmental Planning Section <b>TREE CONSERVATION PLAN APPROVAL</b>			
<b>TCP2- -2017</b>			
Approved by	Date	DRD #	Reason for Revision
		NA	
01 Revision			
02 Revision			
03 Revision			
04 Revision			
05 Revision			

**JM Forestry Services, LLC**  
11552 Timberbrook Drive  
Waldorf, MD 20601  
Phone/FAX: (301) 645-4977

**APPLICANT / DEVELOPER**

Edna and Emmanuel Edokobi  
2006 Stratton Drive  
Potosomac, Maryland 20854-6137  
Phone 301-793-2882

**Natural Resource Inventory and Type 2 Tree Conservation Plan**

**6900 Cipriano Road**  
7th ELECTION DISTRICT  
PRINCE GEORGE'S COUNTY, MARYLAND

REVISIONS	
DWN	Checked
JPM	JPM
Scale	<b>1" = 30'</b>
Project No.	<b>17-017</b>
Sheet No.	<b>2 of 2</b>