

THE SECOND INSPECTION SHALL OCCUR AFTER PLACEMENT OF SEDIMENT CONTROL DEVICES AND/OTE: TREE PROTECTION DEVICES, AND PRIOR TO CLEARING AND GRADING. THIS INSPECTION IS TO

PRE-PLANTING INSPECTION IS TO MAKE FINAL DECISIONS REGARDING THE BEST IMPLEMENTATION

OF PLANT SPECIES. DETERMINATION OF THE REGENERATION POTENTIAL OF EXISTING PLANTS TO REMAIN. AND A DETERMINATION OF THE BEST EDGE PLANTING TREATMENT. THE PURCHASE AND

DELIVERY OF PLANT MATERIALS SHOULD NOT BE MADE UNTIL AFTER THIS INSPECTION SINCE A DETERMINATION MAY BE MADE IN THE FIELD TO ALTER THE CHOICE OF PLANT MATERIAL.

REFORESTATION PLANTING. THIS INSPECTION IS TO DETERMINE THE COMPLETION AND ADEQUACY

MAINTENANCE PROGRAM. THE PURPOSE OF THIS INSPECTION IS TO DETERMINE THE SUCCESS

AND ADEQUACY OF THE MAINTENANCE PROGRAM (AND DEER MANAGEMENT PROGRAM). A FINAL

DETERMINATION WILL BE MADE AT THIS TIME AS TO WHETHER ADDITIONAL PLANTINGS AND A

IN AREAS WITH SUBTANTIAL GROWTH OF INVASIVE GROUNDCOVER SPECIES, MEASURES SHALL BE TAKEN TO REMOVE AND CONTROL INVASIVES. THE INFESTED AREAS SHOULD BE MOWN PRIOR TO COMMENCEMENT OF PLANTING. NECCESSARY WEED CONTROL MEASURES SHOULD BE DETERMINED DURING THE PRE-PLANTING INSPECTION, INCLUDING, BUT NOT LIMITED TO, MULCHING, PERIODIC DURING THE PRE-PLANTING INSPECTION, INCLUDING, BUT NOT LIMITED TO, MULCHING, OF CHINAGE.

WEED CONTROLS WILL BE LIMITED TO EXTREME CASES AND, AND ONLY WITH PRIOR WRITTEN APPROVAL BY MNCPPC STAFF. WHERE PERIODIC MOWING WILL OCCUR AS A WEED CONTROL MEASURE, THE TYPICAL TREE PLANTING DISTRIBUTION PATTERN SHOULD BE MODIFIED SO AS TO

SOILS SHOULD BE TREATED BY INCORPORATING NATURAL MULCH WITHIN THE TOP 12 INCHES, OR AMENDMENTS AS DETERMINED BY THE SOILS ANALYSIS. NATURAL AMENDMENTS, SUCH AS

IF FILL MATERIAL IS USED AT THE PLANTING SITE, IT SHOULD BE CLEAN FILL WITH 12 INCHES OF NATIVE SOIL. STOCKPILING OF NATIVE TOP SOILS MUST BE DONE IN SUCH A WAY THAT THE

MATERIALS WHICH ARE LEFT UNPLANTED FOR MORE THAN 24 HOURS SHOULD BE PROTECTED FROM DIRECT SUN AND WEATHER AND KEPT MOIST. NURSERY STOCK SHOULD NOT BE LEFT UNPLANTED FOR MORE

PRIOR TO PLANTING, PLANTING STOCK SHOULD BE INSPECTED. PLANTS NOT CONFORMING TO STANDARD NURSERYMAN SPECIFICATIONS FOR SIZE, FORM, VIGOR, ROOTS, TRUNK WOUNDS, INSECTS, AND DISEASE

CONTAINER GROWN STOCK: SUCCESSFUL PLANTING OF CONTAINER GROWN STOCK REQUIRES CAREFUL SITE PREPARATION AND INSPECTION OF THE PLANT MATERIAL ROOT SY S RECOMMENDED WHEN SELECTING PLANTS GROWN IN A SOILS MEDIUM DIFFF THAT OF THE PLANTING SITE. THE PLANT SHOULD BE REMOVED FROM THE ROOTS GENTLY LOOSENED FROM THE SOILS. IF THE ROOTS ENCIRCLE TH

SUBSTITUTION IS STRONGLY RECOMMENDED. J-SHAPED OR KINKED ROOT SYL MASS LAOULD

LSO BE NOTED, AND SUBSTITUTED IF NECESSARY. ROOTS MAY NOT BE TRIMMED ON-SITE, DUE TO THE INCREASED CHANCES OF SOIL BORNE DISEASES. THE PLANTING FIELD SHOULD BE PREPARED AS SPECIFIED. NATIVE STOCKPILED SOILS SHOULD BE USED TO BACKFILL PLANTING FIELD. RAKE SOILS EVENLY OVER THE PLANTING FIELD AND COVER WITH 2 TO 4 INCHES OF

BALLED AND BURLAPPED TREES: BALLED AND BURLAPPED TREES MUST BE HANDLED WITH

CARE WHILE PLANTING. TREES SHOULD NOT BE PICKED UP BY THE TRUNK OR DROPPED, AS BOTH PRACTICES WILL TEND TO SEPARATE THE TRUNK FROM THE ROOT BALL. PROIR TO PLANTING,

PLANTING FIELDS SHOULD BE CREATED EQUAL TO 2.5 TIMES THE DIAMETER OF THE ROOT BALL. USE WATERING TO SETTLE SOIL BACKFILLED AROUND TREES. STOCKPILED NATIVE TOP SOILS, IF AVAILABLE, SHOULD BE USED TO BACKFILL THE PLANTING FIELD. AMENDMENTS ARE NOT

RECOMMENDED IN THE PLANTING FIELD, AS STUDIES HAVE SHOWN THAT ROOTS WILL BE ENCOURAGED TO STAY WITHIN THE AMENDED SOILS. SOILS SHOULD BE RAKED EVENLY OVER

RECOMMENDED DUE TO THE INCREASED OPPORTUNITIES FOR INSECT INFESTATION AND DISEASE.

STAKING OF TREES IS NOT RECOMMENDED EXCEPT IN AREAS OF HIGH WINDS. MOVEMENT IS NECESSARY TO STRENGTHEN THE TRUNK OF THE PLANTED TREE. IF STAKES ARE USED, THEY

SOIL STABILIZATION: FOR AREAS OF LARGE-SCALE DISTURBANCE, SOILS MUST BE STABILIZED

PROTECTIVE DEVICES: TO PREVENT DAMAGE OF PLANTED AREAS, ALL REFORESTATION AND AFFORESTATION SITES MUST BE POSTED WITH APPROPRIATE SIGNS AND FENCED. CONSTRUCTION

SHOULD BE REMOVED AFTER THE FIRST GROWING SEASON. WRAPPING IS ALSO NOT

THE PLANTING FIELD AND COVERED WITH 2 TO 4 INCHES OF MULCH.

USING A NON-TURF-BUILDING GROUND COVER OR ENGINEERING FABRIC.

equipment shall be prohibited in these areas.

TREE CRITICAL ROOT ZONE

IT IS RECOMMENDED THAT PLANTING OCCUR WITHIN 24 HOURS OF DELIVERY TO THE SITE. PLANT

MOWING AROUND THE REFORESTATION PLANTINGS, AND FABRIC COVERINGS. THE USE OF CHEMICAL

OF THE PLANTING PLAN, INCLUDING, BUT NOT LIMITED TO, THE FINAL PLACEMENT AND SELECTION

THE THIRD INSPECTION SHALL OCCUR PRIOR TO PLANTING IN REFORESTATION AREAS. THIS

THE FOURTH INSPECTION SHALL OCCUR IMMEDIATELY FOLLOWING THE COMPLETION OF THE

THE FIFTH AND FINAL INSPECTION SHALL OCCUR AT THE COMPLETION OF THE TWO-YEAR

DETERMINE THE COMPLETION AND ADEQUACY OF PROTECTIVE MEASURES.

ALLOW ACCESS BY MOWING EQUIPMENT WITHOUT DAMAGE TO PLANTINGS.

ORGANIC MULCH OR LEAF MOLD COMPOST ARE PREFERRED.

HEIGHT OF THE PILE DOES NOT DAMAGE THE SEED BANK

A SOILS ANALYSIS WILL BE CONDUCTED PRIOR TO COMMENCEMENT OF REFORESTATION. ON LAND WHERE EXTENSIVE AGRICULTURAL USE HAS OCCURED IN THE PAST, TEST PITS WILL BE DUG IN AREAS OF UNDISTURBED SOIL TO DETERMINE IF A FRAGIPAN LAYER IS PRESENT. F FRAGIPAN IS PRESENT, IT SHOULD BE PIERCED BY AUGURING AND PLANTING HOLES

SHOULD BE DUG TO TWICE THE NORMAL DIAMETER FOR THE MATERIAL PLANTED.

FURTHER MAINTENANCE PROGRAM ARE NECCESSARY.

OF THE PLANTING.

2. PRE-PLANTING CONSIDERATIONS


3. PLANT MATERIAL STORAGE

ON-SITE INSPECTION


SHOULD BE REPLACED. PLANTING SPECIFICATIONS

6. POST-PLANTING CONSIDERATIONS

ROOT BALLS SHOULD BE KEPT MOIST.




TYPICAL TREE PLANTING DETAIL




D THE


TYPICAL EVERGREEN TREE PLANTING DETAIL



TYPICAL SHRUB PLANTING DETAIL



-AERATION MAT



PLANTING DISTRIBUTION PATTERNS REFORESTATION AREAS AGGREGATE DISTRIBUTION DRIFT TYPICAL FOREST TREE DISTRIBUTION PATTERNS RANDON NONRANDOM NONRANDOM CLUMPED

POSITIVE ASSOCIATION NEGATIVE ASSOCIATION

SPECIES 2 NOTE:
NATURALLY OCCURING POPULATIONS OF TREESTEND TO BE FOUND
IN INFORMAL GROUPINGS. A CLUSTER OF TREES IS REALLY A MOSAIC
OF DIFFERENT SPECIES GROUPS. THE OBJECTIVE OF AN AFFORESTATION/ REFORESTATION PLAN IS TO SELECT THE APPROPRIATE SPECIES AND DISTRIBUTION PATTERN FOR A CHOSEN SITE THAT WIMICS NATURAL MIXING TRANSPLANT STOCK **** PROTECTIVE FENCING * WIRSERY STOCK

TREE CONSERVATION PLAN NOTES

1. Cutting or clearing of woodland not in conformance with this Plan of without the express written consent of the Planning Director or designee shall be subject to a \$1.50 per square foot mitigation fee. 2. The Department of Environmental Resources (DER) Site Developement Inspector must be contacted at (301) 883-5390 prior to the start of any work on the site to address implementation of any work on the site to address implementation of Tree Conservation measures shown on this Plan. 3. Property owners shall be notified by the Developer or Contractor of any Woodland Conservation Areas (Tree Sove Areas, Reforestation Areas, Afforestation Areas, or Selective Clearing Areas) located on their lot or parcel of land and the associated fines for unauthorized disturbances to these areas. Upon the sale of the property the owner/developer or owners representative shall notify the purchaser of the property of any Woodland Conservation Areas.

4. All appropriate bonds will be posted with the Building Official prior to the issuance of any permits. These bonds will be retained as surety by the Building Official unit all required activities have been satisfied. 5. The location of all Tree Protective Devices (TPD's) shown on this Plan shall be flagged or staked in the field prior to the pre-construction meeting with Site Developement Inspector of DER and the Sediment Erosion Control Inspector from DER and upon approval of the flagged or staked TPD locations by the DER Site Development Inspector, installation of the TPD's may begin. TPD installation shall be completed prior to installation of initial Sediment Controls. No cutting or clearing of trees may begin before final approval of TPD

6. Woodland Conservation — Tree Save Areas and/or Reforestation Areas shall be posted as shown at the same time as Tree Protective Device installation and/or start of reforestation activities. These signs shall remain in place and may be removed after final grading has be removed after house construction has been completed and the new house owner has

WOODLAND CONSERVATION AREA MANAGEMENT NOTES Removal of Hazardous Trees or Hazardous Limbs By Developers or Builders The developer and/or builder is responsible for the complete preservation of all forested areas shown on the approved plan to remain undisturbed. Only trees or parts thereof designated by the Department of Environmental Resources as dead, dying, or hazardous may be removed. A tree is considered hazardous if a condition is present which leads a Licensed Arborist or a Licensed Tree

Expert to believe that the tree or a portion of the tree has a potential to fall and strike a structure, parking area, or other high use area and result in personal injury or property damage. 2. If a hazardous condition may be alleviated by corrective pruning, the Licensed Arborist or a Licensed Tree Expert may proceed without further authorization. The pruning must be done in accordance with the latest edition of the ANSI A300 Pruning Standards ("Tree, Shrub, and Other Woody Plant Maintenance

Corrective measures requiring the removal of the hazardous tree or portions thereof shall require authorization by the building or grading inspector if there is a valid grading or building permit for the subject lots or parcels on which the trees are located. Only after approval of the appropriate inspector may the tree be cut by chainsaw to near the existing ground level. The stump may not be removed or covered with soil, mulch or other materials that would inhibit sprouting.

Debris from the tree removal or pruning that occurs within 35 feet of the woodland edge may be removed and properly disposed of by recycling, chipping or other acceptable methods. All debris that is more than 35 feet from the woodland edge shall be cut up to allow contact with the ground, thus encouraging decomposition. The smaller materials shall be placed into brush piles that will serve as wildlife habitat.

Removal of Hazardous Trees, Hazardous Limbs, Noxious Plants, Invasive Plants or Non -Native Plants in Woodland Conservation Areas Owned by Individual Homeowners

If the developer or builder no longer has an interest in the property the home owner shall obtain a written statement from the Licensed Arborist or Licensed Tree Expert identifying the hazardous condition and the proposed corrective measures prior to having the work conducted. The tree may then be removed by the arborist or tree expert. The stump shall be cut as close to the ground as possible and left in place. The removal or grinding of the stumps in the woodland conservation area is not permitted.

The removal of noxious, invasive, and non-natives plant species from the woodland conservation areas may be done with the use of hand-held equipment only such as pruners or a chain saw. These plants may be cut near the ground and the material less than two inches diameter may be removed from the area and disposed of appropriately. All material from these noxious, invasive, and non-native plants greater than two (2) inches diameter shall be cut to allow contact with the ground, thus encouraging decomposition.


The use of broadcast spraying of herbicides is not permitted. However, the use of herbicides to discourage re-sprouting of invasive, noxious, or non-native plants is permitted if done as an application of the chemical directly to the cut stump immediately following cutting of plant tops. The use of any herbicide shall be done in accordance with the label instructions.

Note: The use of chainsaws is extremely dangerous and should not be conducted with poorly maintained equipment, without safety equipment, or by individuals not trained in the use of this equipment for the pruning and/or cutting of trees.


Protection of Reforestation Areas by Developers or Builders

Reforestation areas shall be planted prior to the occupancy of the nearest building or residence. If planting cannot occur due to planting conditions, the developer or property owner shall install the fencing and signage in accordance with the approved Type II Tree Conservation Plan. Planting shall then be accomplished during the next plantin g season. If planting is delayed beyond the transfer of the property title, to the homeowner, the developer shall obtain a signed statement from the purchaser indicating that they understand that the reforestation area is located on their property and tha t reforestation will occur during the next planting season. A copy of that document shall be presented to the Grading Inspector and the Environmental Planning Section.

Reforestation areas shall not to be mowed, however, the management of competing veg etation around



REFORESTATION AREAS SCALE 1"=40



ONSITE REFORESTATION PLANTING SCHEDULE FOR 0.24 ACRES (CREDIT FOR 0.1 ACRES OF PLANTING COVERED BY STORM WATER MANAGEMENT LANDSCAPING AREA 6, SEE LANDSCAPING PLAN SHEET 2 FOR DETAILS) QTY KEY BOTANICAL NAME SIZE/TYPE ROOT CONDITION REMARKS QUERCUS RUBRA NORTHERN RED OAK LIRIODENORON TULIPIFER TULIP POPLAR PRUNUS SEROTINA BLACK CHERRY QUERCUS PALUSTRIS PIN OAK 2" CAL 888 PLATANUS OCCIDENTALIS AMERICAN SYCAMORS 2" CAL 5&B EVERGREEN TREES 3 10(1) ILEX OPACA AMERICAN HOLLY (FEMALE) 4" - 5" HEIGHT 888 1 (0(m) ILEX OPACA AMERICAN HOLLY (MALE) 4" - 5" HEIGHT SMALL TREES CERCIS CANADENSIS EASTERN REDBUD 1" CAL 8 & 8 AMELANCHIER CANADENS! SHADBLOW SERVICEBERRY 888 CARPINUS CAROLINIANA 888

THIS PLAN MODIFIED BY AB CONSULTANTS, INC. AS PER RIGHTS PURCHASED BY OWNER. ALL PROPOSED CHANGES ARE LIMITED TO LOT 2 WOODLAND CONSERVATION ONLY



AB CONSULTANTS, INC. 9450 ANNAPOLIS ROAD LANHAM, MARYLAND 20706

PHONE: (301) 306-3091

FAX: (301) 306-3092

CONTACT: CHINMAY VYAS, PE PHONE: 301-306-3091 x 22

CALL "MISS UTILITY" 1-800-257-7777 FOR UTILITY LOCATIONS AT LEAST 48 HOURS BEFORE BEGINNING CONSTRUCTION

Protection of Reforestation and Afforestation Areas by Individual Homeowners

individual trees is acceptable.

Environmental Planning Section.

of Kentucky 31 fescue is not acceptable.

Conservation Plan or untilthe trees have grown sufficiently to have crown closure.

Woodland Areas NOT Counted as Part of the Woodland Conservati on Requirements

Reforestation fencing and signage shall remain in place in accordance with the approved Type II Tree

Reforestation areas shall not to be mowed, however, the management of competing vegetation around

identified to be cleared on the most recently approved Type II Tree Conservation (TCP) on file in the office

A revised Tree Conservation Plan is required prior to clearing any woodland area which is not specifically

of the M-NCPPC, Environmental Planning Section located on the 4 th flood of the County Administration

Building at 14741 Governor Oden Bowie Drive, Upper Marlboro, Maryland 20772, phone 301 -952-3650.

requirements, mitigation, and fees which must be reflected on TCP revisions approved by the M NCPPC

Homeowners or property owners may remove trees less than two (2) inches diameter, shrubs, and vines in woodland areas which are saved but not part of the Woodland Conservation requirements after all permits


have been released for the subject property. This area may not be tilled or have other ground disturbances

native flowers or native ground covers is acceptable. Seeding with invasive grasses including any variety

which would result in damage to the tree roots. Raking the leaves and overseeding with native grasses,

Additional mitigation will be required for the clearing of all woodlands beyond that reflected on the

approved plans. Although clearing may be allowed, it may be subject to additional replacement



Prince George's County Planning Departme Environmental Planning Section APPROVAL TREE CONSERVATION PLAN TCP II/7/03 JOHN MARKOVICH 01* | LORI SHIRLE

* REFER TO DEWBERRY REVISION BLOCK FOR

DESCRIPTION OF 01 REVISION

ewberry

(J)

avi

N KEA

ROJECT NO. RX845 AS SHOWN CALE:

SHEET