

	SOIL TYPES	
	AIN / POORLY DRAINED	a and t
Во	Bibb silt loam	0-2% slopes
lk	luka fine sandy loam	0-5% slopes
	Shrewsbury fine sandy loam	0-2% slopes
SnA	Shrewsbury silt loam	0-2% slopes
MODERAT	TELY WELL DRAINED	
AdA	Adelphia fine sandy loam	0-2% slopes
	Adelphia fine sandy loam	2-5% slopes
	Adelphia silt loam	0-2% slopes
AhB2	Adelphia silt loam	2-5% slopes
WELL DR	AINED	
	Collington fine sandy loam	2-5% slopes
	Collington fine sandy loam	5-10% slopes
CmC3	Collington fine sandy loam	5-10% slopes
CmD3	Collington fine sandy loam	10-15% slopes
	Collington fine sandy loarn	15-40% slope:
	Collington fine sandy loam	15-30% slope:
	Howell clay loam	6-12% slopes
HoB2	Howell fine sandy loam	2-6% slopes
	Howell silt loam	0-6% slopes
OcB		2-5% slopes
	Westphalia fine sandy loam	0-2% slopes
	Westphalia fine sandy loam	2-6% slopes
	Westphalia fine sandy loam	
	Westphalia fine sandy loam	
	Westphalia fine sandy loam	
WaD3	WESTORGIG RUE SURIUS RADIO	L 20/0 31000

		SPECIMEN,	CHAMIPI	ON AND HE	STOME II	NEE TADLE	
No.	Common Name	Scientific Name	DBH (inches)	Condition Rating	Condition Score*	Condition Comments	Disposition
T62	Southem Red Oak	Quercus falcata	37	Poor	22	broken limbs	To be Removed by Others
T63	Yellow Poplar	Liriodendron tulipifera	56	Poor	22	hollow trunk/lightning strike	Saved
T64	Dead						Removed
T65	Yellow Poplar	Liriodendron tulipifera	44	Poor	20	hollow trunk	Saved
Т66	Yellow Poplar	Liriodendron tulipifera	44	Excellent	31		Saved
T67	Yellow Poplar	Liriodendron tulipifera	43	Good	28		Saved
T68	Northern Red Oak	Quercus rubra	31	Good	28		Saved
T69	Dead						Saved
T70	American Beech	Fagus grandifolia	34	Good	27		Saved
T71.	Dead						Saved
T72	Yellow Poplar	Liriodendron tulipifera	55	Fair	24		Saved
T73	Dead						Saved
T74	Yellow Poplar	Liriodendron tulipifera	47	Poor	18	exposed roots on steep bank	Saved
T75	Dead						To Remain As-l

PRINCE GEORGE'S COUNTY, MARYLAND


TREE CONSERVATION PLAN


NORTH VILLAGE SECTIONS 4 & 5 BASIC PLAN A-9763-C COMPREHENSIVE DESIGN PLAN CDP-9706 PRELIMINARY PLAN 4-00010 AREA PART OF THIS APPLICATION **LEONNIG** LIBER 8481, FOLIO 816 ZONE RA USE: AORICULTURAL

- BEECHWOOD

HISTORIC SITE

FUTURE CSC





VICINITY MAP SCALE 1"=2000'

SHEET INDEX

3-9

DESCRIPTION

TREE CONSERVATION PLANS, 1"=30'

COVER SHEET, KEY MAP

DETAIL SHEET


--- EXISTING CONTOUR PROPOSED SPOT ELEVATION STEEP SLOPES, 15-25% STEEP SLOPES, >25% EX. PROPERTY LINE PROPOSED RIGHT-OF-WAY PROPOSED PARCEL LINE SOIL BOUNDARY SOIL CLASSIFICATIONS EXISTING TREE LINE EXISTING SHRUB LINE SPECIMEN TREE NON-TIDAL WETLANDS 25' WETLAND BUFFER ------ 100-YEAR FLOODPLAIN PRIMARY MANAGEMENT AREA EX. 10" WATER EXISTING WATER LINE EX. 10" SEWER EXISTING SEWER LINE PROPOSED PARCEL PROPOSED BLOCK PROPOSED SHADE TREE PROPOSED EVERGREEN TREE PROPOSED ORNAMENTAL TREE PROPOSED SHRUBS FACTOR OF SAFETY LINE



NOTE: TCP 2-025-10 WAS SEPARATED FROM TCP 2-049-98 WITH THE APPROVAL OF SDP-0409-02.

TREE CONSERVATION

AREA SIGNAGE



NV 4 & 5

VOB LIMITED PARTNERSHI TYSONS OFFICE CENTER 8133 LEESBURG PIKE, SUITE 300 VIENNA, VA 22182 703-288-4200 FAX:703-288-4218

HOUSE ARCHITECTURAL DRAWINGS FOR PROPOSED SINGLE-FAMILY RESIDENTIAL UNITS HAVE BEEN APPROVED UNDER SDP-0001 AND SDP-0315

M.N.C.P.P.C. APPROVALS

PROJECT NAME: BEECH TREE

PROJECT NUMBER: SDP-0409

OWNER/DEVELOPER:

M-NCPPC

Environmental Planning Section

TREE CONSERVATION PLAN

TCP 2-025-10

GREENMAN-PEDERSEN, INC. ENGINEERS, ARCHITECTS, PLANNERS, CONSTRUCTION ENGINEERS & INSPECTORS 10977 GUILFORD ROAD, ANNAPOLIS JUNCTION, MD. 20701 WASH. (301) 470-2772 BALT. (410) 880-3055 FAX: (301) 490-2649 www.gpinet.com

10/06/2006 REVISED TO 80' LOTS, REVISED BLOCKS 5/06/2006 REVISED PER 65' LOTS

W SERVON BELT LIBER JBB 6 FOLIO 233 ZONE: RE

USE: AGRICULTURAL

MARLBORD MANOR

PART OF PARCEL 101 P.B. 160 P.No. 10

M.N.C.P. & P.C. LIBER 9879, FOLIO 522

CHARLES K. KILDY LIBER 10244, FOLIO 524

USE RESIDENTIAL

AMMR S. BAMSADAR LIBER 3010, FOLIO 12 CASES APARTMENTS

ZZONE: RV

W. SEATON BELT LIBER JBB 6, FOLIO 2003 ZONE: RE USE: AGRICULTURAL

SECTIONS OF BEECH TREE THAT HAVE BEEN APPROVED TO DATE.


NOT PART OF THIS APPLICATION


PENTLAND HILLS
HISTORIC SITE

(IN FEET) 1 inch = 600 ft.

General Tree Conservation Notes:


- 1. Cutting or clearing of woodland not in conformance with this plan or without the expressed written consent of the Planning Director or designee shall be subject to a \$1.50 per square foot mitigation fee.
- 2. The Department of Environmental Resources (DER) Inspector must be contacted prior to the start of any work on the site to address implementation of Tree Conservation measures shown on 3. All appropriate bonds will be posted with the Building Official prior to the issuance of any permits. These bonds will be retained as surety by the Building Official until all required activities
- have been satisfied. 4. The location of all Tree Protection Devices (TPDs) for areas of preservation shown on this Plan shall be flagged or staked in the field prior to the pre-construction meeting with the inspector from DER. Upon approval of the flagged or staked TPD locations by the DER Inspector, installation of the TPDs may begin. TPD installation shall be completed prior to installation of initial Sediment Controls. No cutting or clearing of trees may begin before final approval of TPD installation. 5. Since work on this project will be initiated in several phases all TPDs required for a given
- phase shall be installed prior to any disturbance within that phase of work. 6. Woodland Conservation - Tree Save Areas shall be posted as shown at the same time as Tree Protective Device installation. The signs shall remain in place in perpetuity. 7. Roots of all trees within 20 feet of the limits of disturbance shall be cut along the limits of disturbance to a depth of at least 18 inches using a vibratory plow (cable laying machine) or toothed chain trencher, prior to installation of Tree Protective Devices or start of grading. 8. Contractor is liable for any damages he causes during construction to any preservation areas, fences, roads, paved paths, utilities, or other improvements on private or public property. 9. Approved Sediment and Erosion Control Measures may be substituted in lieu of Tree Protective Devices (TPDs) shown on this plan. In-field location and substitutions must be approved by the
- DER Inspector. 10. Tree Protection Device shown below (Detail 1) is to be used for both preservation and reforestation areas.






BLAZE ORANGE PLASTIC MESH

- 1. TREE PROTECTIVE DEVICE LOCATIONS WILL CORRESPOND TO THE LOCATIONS SHOWN ON THIS TREE CONSERVATION PLAN. 2. FENCE POSTS WILL BE A MINIMUM OF 1 3/4 " X 1" STEEL U-CHANNEL OR 2" X 2" LUMBER, SPACED NO MORE THAN 8 FEET APART. POSTS WILL BE INSTALLED AT LEAST 2 FEET DEEP.
- 3. SMOOTH WIRE SHOULD BE EVENLY SPACED ALONG THE HEIGHT OF THE POSTS, AND FASTENED SECURELY TO THE POSTS. MINIMUM ACCEPTABLE WIRE IS "LIGHT GUAGE, CLASS 1", GALVANIZED.
- 4. TREE CONSERVATION AREA SIGNS WILL BE SECURELY ATTACHED TO AT LEAST EVERY FIFTH POST AND SHALL REMAIN IN PLACE IN PERPETUITY. 5. SEDIMENT AND EROSION CONTROL MEASURES WILL COMPLY WITH THE SEDIMENT CONTROL PLAN AS APPROVED BY THE PRINCE GEORGE'S COUNTY SOIL CONSERVATION DISTRICT, AND MAY INCLUDE COMBINATIONS OF SEDIMENT CONTROL FENCING WITH TREE CONSERVATION AREA PROTECTIVE DEVICE FENCING, IF SO
- 6. TREE PROTECTIVE DEVICES WILL BE ERECTED IMMEDIATELY AFTER TREE AND SHRUB PLANTING IS COMPLETED, AND REMOVED AFTER THE FINAL (5 YEAR) SURVIVAL CHECK. THE CONTRACTOR WILL ADVISE THE OWNER IN WRITING WHEN THIS WORK IS COMPLETED.





REATED TCP II PLANS

TYP

CMR

ESIGNED

G.P.I.

NRB


HECKED

CMR

RAWN

1. SIGN TO BE LAMINATED CARDBOARD OR PLASTIC 2. BOTTOM OF SIGNS TO BE HIGHER THAN TOP OF TREE PROTECTION FENCE. 3. TREE CONSERVATION AREA SIGNS WILL BE SECURELY ATTACHED TO AT LEAST EVERY FIFTH POST AND SHALL REMAIN IN PLACE IN PERPETUITY. TREE CONSERVATION SIGN

REVISIONS



REFORESTATION DETAIL LEGEND

RED MAPLE M AMERICAN HOLLY O PIN OAK ☐ SWEETGUM

REFORESTATION PLAI	NT SCHE	DULE
SPECIES	CONDITION	QUANTITY/A
ACER RUBRUM - RED MAPLE	WHIP	100 (20%
QUERCUS PALUSTRIS - PIN OAK	WHIP	150 (30%
LIQUIDAMBER STYRACIFLUA - SWEETGUM	WHIP	150 (30%
ILEX OPACA - AMERICAN HOLLY	WHIP	100 (20%
		500

1,000 Seedling Equivalents per Acre, and that a Whip is the Equivalent to Two Seedlings, so that 500 Whips per Acre Satisfies the Requirement. Reforestation Notes:

1. Seedlings will be hand planted using random distribution of species and locations, at an average of 500 inch catipers per acre, utilizing the "Dibble Planting Method". 2. Seedlings will be graded for quality, especially root systems, before planting, and come from local sources.


3. Contractor will provide for proper care of seedlings, including during transport, in storage, and handling in the field. 4. Any tree shown by inspection within 30 days of planting to be improperly planted will be replaced and properly planted with new trees of the same type and specifications. If 20% or more of seedlings are improperly planted, the entire stand may be required to be replaced with new trees properly planted, or the total cost of the trees and replanting repaid to the owner, at the owner s

5. The planting contractor shall guarantee a minimum of 75% survival of the plants for 5 years from date of planting. Plants will be field checked at least three times during the first year, with watering if needed and control of undesirable vegetation if needed. Plants will be field checked two times during the second and third years with reinforcement planting if needed and control of undesirable vegetation if needed. Plants will be field checked one time during the fourth and fifth years with reinforcement planting if needed. Records of survival to be maintained during the field checks. Field data forms will be sent to the client after each visit. (See Tee Condition Check Sheet on plan.) Dead plants will be replaced to maintain at least 75% survival. Perimeter fencing and signage will be removed after year 5 based on the date planted. 6. Contractor will locate all existing utilities prior to start of operations.

Contractor to adjust plant locations to avoid existing utilities and maintain existing easements. New plant locations to be approved by the County and/or Urban Forester. 8. Contractor is liable for damages caused to any utilities, including any repairs, at no additional cost to the owner. 9. Contractor is liable for damages he causes during planting to any fences, roads, paved paths, other improvements on private or public property.

10. Twenty-five percent (25%) of Afforestation requirements met through the use of landscape plant materials in Afforestation areas. 11. All reforestation/afforestation areas adjacent to lots, and split rail fencing along the outer edge of all reforestation/afforestation areas shall be installed prior to lissuance of use and occupancy permits for the adjacent lots.

HANDLING AND PLANTING OF SEEDLING(2)




Seedlings dry out very quickly and, once dry, often are not usable even after moistening.

SEEDLING PLANTING METHODS

I. INSERT DIBBLE AT

ANGLE SHOWN ABOVE




AND PUSH FORWARD CORRECT DEPTH. PLANTER FROM SEEDLING TO UPRIGHT POSITION. SOURCE: adapted from the Maryland State FOREST CONSERVATION MANUALL

2. REMOVE DIBBLE AND PLACE SEEDLING AT

S. INSERT DIBBLE

2 INCHES TOWARD

HANDLING AND PLANTING OF SEEDLING(3)



TOWARD PLANTER FIRMING SOIL AT BOTTOM OF

8. FILL LAST HOLE BY 9. FIRM SOIL ARROUND STAMPING WITH HEEL. SEEDLING WITH FEET

. PULL FORWARD THEN PULL BACKWARD FILLING 3. MATTOCK PLANTING 2. PLACE SEEDLING ALONG 3. FILL IN AND PPACK SOIL . INSERT MATTLOCK, LIFT STRAIGHT SIDE AT TO BOTTOM OF ROOTS. CORRECT DEPTH. 4. FIRM AROUND SEEDLING 5. FINISH FILLING IN SOIL

SOURCE: adapted from the Maryland State FOREST CONSERVATION MANUALL

REVISIONS

SPECIFICATIONS FOR PLANTING

Plant Identification: All plants shall be properly marked for identification. List of Plant Material

The Contractor will verify the plant quantities prior to bidding and any discrepancies shall be brought to the attention of the Landscape Architect. The Contractor shall furnish and plant all plants required to complete the work shown on the drawings. Substitution shall not be made without the written approval of the Landscape Architect. This Contract will be based on the bidder having verified prior to bidding, the availability of the required plant material as specified on the Plant Materials List, Plant Quality

All shrubs shall be dense, heavy to the ground, and well grown, showing evidence of having been sheared regularly, and shall be sound, free of plant disease or insect eggs and shall have a healthy normal root system. Plants shall be freshly dug and not heeled-in stock, nor from cold storage. All plants shall be nursery grown (except as noted below). Plants shall not be pruned prior to delivery. The shape of the plant shall in general conform to its natural growth proportions unless otherwise specified. Trees shall conform to the branching, caliber, and height specifications of the American Association of Nurserymen, and shall have a well-shaped, heavy branch structure for the species. Evergreen trees are to have an internode no greater than 18" and shall be uniformly well shaped. All plant sizes shall average at least the middle of the range given in the plant list.

Soil mix will be 2/3 existing soil, 1/3 leafmold or equal organic material,

thoroughly mixed and homogenized.

Holes for all plants shall be 18' larger in diameter than size of ball or container and shall have vertical sides. Hedges shall be planted in a trench 12" wider; beds for mass planting shall be entirely rototilled to a depth of 8' and shall be 18' beyond the average outside edge of plant

Excavation

Backfilling shall be done with soil mix, reasonably free of stones, subsoil, clay lumps, stumps, roots, weeds, bermuda grass, litter, toxic substances, or any other material which may be harmful to plant growth, or hinder grading, planting, or maintenance operations. Should any unforeseen or unsultable planting conditions arise, such as faulty soil drainage or chemical residues, they should be called to the attention of the Landscape Architect and Owner for adjustment before planting. The plant shall be set plumb and straight, and shall be staked at the time of planting. Backfill shall be well worked about the roots and settled by watering. Plants will be planted higher than surrounding grade. Shrubs will be 1" higher and trees will be 3" higher.

All trenches and shrub beds shall be cultivated, edged and mulched to a depth of 3' with fine shredded hardwood bark. The area around isolated plants shall be mulched to at least a 6' greater diameter than that of the hole. Plant beds adjacent to buildings shall be mulched to the building wall. Maintenance

The Contractor shall be responsible during the contract and up to the time of acceptance, for keeping the planting and work incidental thereto in good conditions, by replanting, plant replacement, watering, weeding, cultivating, pruning and spraying, restaking and cleaning up and by performing all other necessary operations of care for promotion of good plant growth so that all work is in satisfactory condition at time of acceptance, at no additional cost to the Owner.

Fertilizer

Fertilizer shall be a slow release type contained in polyethylene perforated bags with micropore holes for controlled feeding such as Easy Grow as manufactured by Specialty Fertilizer, Inc., Box 355, Suffern, New York 10901 or approved equal. The bags shall contain 1 ounce of soluble fertilizer analysis 16-18-18 per units to last for three years and shall be applied during planting as recommended by the manufacturer. If fertilizer packets are not used the Contractor shall apply granular fertilizer to the soil mix with 10-6-4 analysis at the following rates: Tree Pits, 2-3 lbs. per caliper inch; Shrub Beds, 3-5 lbs. per 100 square foot; Ground cover, 2-3 lbs. per 100 square foot.

Ground Cover

All areas of ground cover shall be rototilled to a depth of 6". Apply 2" of organic material and rototill until thoroughly mixed. Apply fertilizer as

Guarantee and Replacement

All materials shall be unconditionally guaranteed for one year. The Contractor is not responsible for losses or damages caused by mechanical injury or vandalism. Guarantee shall cover both labor and materials. Earth saucers and stakes and guys shall be removed and trees, shrubs, and whips mulched to 3" maximum depth with shredded bank just prior to expiration of the one-year guarantee. The owner shall be notified in writing when this work is to occur.

Plant Spacing

Plant spacing is generally to scale on plan. Shrub spacing is noted in the plant list. No plants except viney ground covers or espallered material shall be closer than 30" to building, walks or curbs.

WOODLAND CONSERVATION AREA EDGE MANAGEMENT NOTES Prepared by the Environmental Planning Section, Planning Department, M-NCPPC Revised 4/23/2003


Removal of Hazardous Tree or Hazardous Limbs By Developers or Builders


The Devoloper and/or builder is responsible for the complete preservation of all forested areas shown on the approved plan to remain undisturbed. Only trees or parts thereof designated by the Department of Environmental Resources as dead, dying or hazardous may be removed.


- 1. A tree is considered hazardous if a condition is present which leads a Licensed Arborist or a Licensed Tree Expert to believe that the tree or a portion of the tree has a potential to fall and strike a structure, parking area or other high use area and result in personal injury or property damage.
- 2. If a hazardous condition may be alleviated by corective pruning, the Licensed Arborist or the Licensed Tree Expert may proceed without further authorization. The pruning must be done in accordance with the latest edition of the ANSI A-300 Pruning Standards ("Tree. Shrub, and other Woody Plant Maintenance - Standard Practices").
- Corrective measures requiring the removal of the hazardous tree or portions thereof shall require authorization by the building or grading inspector if there is a valid grading or building permit for the subject lots or parcels on which the trees are located. Only after approval of the appropriate inspector may the tree be cut by chainsaw to neat the existing ground level. The stump may not be removed or covered with soil, mulch or other materials that would inhibit sprouting.


Debris from the tree removal or pruning that occurs within 35 fett of the woodland edge may be removed and properly disposed of by recycling, chipping or other acceptable methods. All debris that is more than 35 feet from the woodland edge shall be cut up to allow contact with the ground, thus encouraging decomposition, The smaller the materials shall be placed into brush piles that will serve as wildlife habitat.

M.1	N.C.P.	P.C. APPROV	ALS
PROJECT	NAME:	BEECH TREE	
PROJECT	NUMBER	: SDP-0409	
For Condition	ns of Approv The Revision	al see Site Plan Cover Sheet or A s Listed Below Apply to this Shee	ipproval Sheet
Approval or Revision #	Approval Date	Reviewer's Signature	Certification Date
	7/11/06	H.Z.	12-1-06
01	8/3/07	J.R.	8-3-07
02_	1/23/1	F09	1/20/1
	1 10		1-1
		*	
			l .









<u> Habitat Management Plan Notes:</u>

BEECH TREE - OVERALL WORKSHEET Last Revised 16-Mar-12

1. No disturbance of woodland is permitted on the site until it is comfirmed that it is consistent with the Habitat Management Plan for the Stripeback Darter approved by the Wildlife and Heritage Division of DNR 2. Prior to the issuance of any grading permit for the site, the Type II TCP shall be revised to incorporate the recommendations of the approved Habitat Management Plan for the Stripeback

the recommendations of the Habitat Management Plan have been incorporated into the TCPII.

3. No grading, cutting, clearing of woodland, or removal of trees is permitted on the site until Protection of Reforestation and Afforestatation Areas by Individual Homeowners

1. Reforestation Fencing and signage shall remain in place in accordance with the approved Type II Tree Conservation Plan or until the trees have grown sufficiently to have crown closure.


2. Reforestation areas shall not to be mowed, however, the management of competing vegetation around individual trees is acceptable

Woodland Areas NOT Counted as Part of the Woodland Conservation Requirements

the office of the M-NCPPC, Environmental Planning Section located on the 4th floor of the County Administration Building at 14741 Governor Oden Bowie Drive, Upper Marlboro, Maryland 20772, phone 301-952-3650. Additional mitigation will be required for the clearing of all woodlands beyond that reflected on the approved plans. Although clearing may be allowed, it may be subject to additional replacement requirements, mitigation and fees which must be reflected on TCP revisions approved by the M-NCPPC Environmental Planning Section.


all permits have been released for the subject property. This area may not be tilled or have other ground disturbances which would result in damage to the tree roots. Raking the leaves and overseeding with native grasses, native flowers or native ground covers is acceptable. Seeding with invasive grasses, including any variety of Kentucky 31 fescue is not acceptable. NOTE: THE SDP-9803 AND ASSOCIATED TCP2 SHEETS SHALL BE REVISED TO REFLECT

WOODLAND CONSERVATION PROVIDED IN ACCORDANCE WITH THIS TABLE PRIOR TO CERTIFICATION OF ANY SDP OR REVISION AFFECTING OVERALL WOODLAND CONSERVATION PROVIDED.



TREE CONSERVATON PLAN TYPE II - WORKSHEET

27 Off-site Mitigation provided on this property 28 Total Woodland Conservation Provided 29 Area of net tract woodland not cleared 6.06 acres 30 Woodland retained not part of requirements: 0.00 acres Prepared by: Name Address Phone License NOTE: TREE CONSERVATION AREA SIGNS WILL BE SECURELY ATTACHED TO AT LEAST EVERY FIFTH POST AND SHALL REMAIN IN PLACE IN PERPETUITY - PRESSURE TREATED SPLIT RAIL . TREE CONSERVATION SIGN SEE DETAIL #2



M-NCPPC Prince George's County Planning Department **Environmental Planning Section** APPROVAL TREE CONSERVATION PLAN TCP 2-025-10 Hench

SPLIT RAIL FENCE (NTS) SPLIT RAIL FENCE TO BE LOCATED AROUND ALL

25 Area approved for fee-in-lieu

26 Credits Received for Off-site Mitigation on another property

AREAS OF AFORESTATION

1. A revised Tree Conservation Plan is required prior to clearing any woodland areas which is not specifically identified to be cleared on the most recently approved Type II Tree Conservation (TCP) on file in


2. Homeowners or property owners may remove treesa less than two (2) inches in dliameter, shrubs and vines in woodland areas which are saved but not part of the Woodland Conservation requirements after

CALL "MISS UTILITY" AT LEAST 48 HOURS IN ADVANCE OF CONSTRUCTION AT 1-800-257-7777

TCP 2-025-10 WAS SEPARATED FROM TCP 2-049-98 WITH THE APPROVAL OF SDP-0409/02.

NOTE: THE COMBINED TOTAL OF APPROVED UNITS FROM 4-00010 AND 4-99026 15 2.351.

OWNER/DEVELOPER: VOB LIMITED PARTNERSHIP TYSONS OFFICE CENTER 8133 LEESBURG PIKE, SUITE 300 VIENNA, VA 22182 703-288-4200 FAX:703-288-4218



THIS PLAN IS FOR TREE CONSERVATION PURPOSES ONLY.

BEECH TREE

TREE CONSERVATION PLAN TYPE II NORTH VILLAGE SECTIONS

DATE PROJECT NO 4/11/2012 97179

Greenman-Pedersen, Inc. Engineers, architects, planners, construction engineers & inspectors 10977 GUILFORD ROAD ANNAPOLIS JUNCTION, MD 20701 WASH. (301) 470-2772 BALT. (410) 880-3055 FAX: (301) 490-2649 www.gpinet.com

Clatest date hereon

, Floodplain: Previously Dedicated Land:

Property Description or Subdivision Name: is this site subject to the 1989 Ordinance? Break-even Point (preservation acres) ≠ Acres of Net Tract clearing permitted w/o re

oodland Conservation Requirement Calcula xisting Woodland on Net Tract (acres)

vocation above WCT Plan Number (This must be completed for each phase)
Plan Revision #
TCPII #
TCPII Revision #
Plan Phase or Name:

Floodplain area in this application (acres)
Net Tract area in the application (acres)
Woodland on the Net Tract for this phase (acres)

loodland in the Floodplain for this phase loodland Cleared on Net Tract for this phase

Woodland Cleared in Floodplain for this phase Woodland Cleared in PMA outside of FP (1:1)

Commutative actes or Floorplain woodand cleared Smaller of d or e Woodand Clearing below WCT Replacement for clearing above the WCT (0.25 : 1) Replacement for clearing below the WCT (2 : 1) Afforestation Threshold (AFT) = Climidative Woodland Conservation Required

Woodland Conservation Provides

Afforestation /Reforestation Afforestation/Reforestation (PMA) Natural Regeneration (PMA_ atural Regeneration rea approved for fee-in-lieu

Credit for Off-site Miligation on another properly Off-site Miligation provided on this property

Preservation

Pian Status Approval Date Permit Status Total area in this application (ecres)


PRINCE GEORGE'S COUNTY, MARYLAND


MARLBORO (37) ELECTION DISTRICT


PA. 79 UPPER MARLBORO & VICINITY


4 & 5


SHEET SCALE AS SHOWN N:\1997\97179\DWG\Fvil\FV-11\TCPILDFT_01NV-45 dv














REVISIONS

N:\1997\97179\DWG\NVIL\NV45SDP\TCPII 03NV45.DWG EC00, EF00, BA00, PC00, VMAP

