

Property owners shall be notified by the Developer or Contractor of any Woodland Conservation Areas (Tree Save Areas, Reforestation Areas, Afforestation Areas, or Selective Clearing Areas) located on their lot or parcel of land and the associated fines for unauthorized disturbances to these areas. Upon the sale of the property the owner / developer or owners representative shall notify the purchaser of the property of any Woodland Conservation Areas.

shall be contacted prior to the start of any work on the site

to address implementation of woodland conservation measures

4. All appropriate bonds shall be posted with the Building Official prior to the issuance of any permits. These bonds will be retained as surety by the Building Official until all required activities have been satisfied. 5. All required off-site mitigation shall be identified on an approved TCPII for the off-site location and shall be recorded as an off-site easement in the land records of Prince George's County prior to issuance of any permits for the subject 6. The location of all Tree Protective Devices (TPDs) shown on this Plan shall be flagged or staked in the field prior to the


pre-construction meeting with the Sediment and Erosion Control Inspector from DPW&T. Upon approval of the flagged of staked TPD locations by the Inspector, installation of the TPDs may begin. TPD installation shall be completed prior to installation of initial Sediment Controls. No cutting or clearing of trees may begin before final approval of TPD installation.

Woodland Conservation - Tree Save Areas and/or Reforestation treas shall be posted as shown at the same time as Tree Protective Device installation and/or start of reforestation activities. These signs shall remain in place.


8. All tree planting for woodland replacement, reforestation or afforestation will be completed prior to Use and Occupancy
Permit, Failure to establish the woodland replacement, reforestation or afforestation within the prescribed time frame will result in the forfeiture of the Reforestation Bond and/or a violation of this Plan including the associated \$1.50 per square foot penalty unless a written extension is approved by the DPW&T


The DPW&T Inspector shall be notified prior to soil preparation or initiation of any tree planting on this site. 10. Results of survival checks for all tree plantings shall be reported to the DPW&T Inspector for the site and M-NCPPC, Environmental Planning Section.

... Prior to the issuance on any permits the contractor responsible for soil preparation, site preparation, tree planting and tree maintenance must be identified.



1. INVASIVE PLANT REMOVAL SHALL BE COMPLETED PRIOR TO TREE PLANTING AND CONFORM TO THE RECOMMENDATIONS OF THE INVASIVE PLANT REMOVAL PLAN SHOWN ON THE PLAN PREPARED BY JM FORESTRY 2. THE REMOVAL OF NOXIOUS, INVASIVE, AND NON-NATIVE PLANT SPECIES SHALL BE DONE WITH THE USE OF HAND-HELD EQUIPMENT ONLY SUCH AS PRUNERS OR A CHAIN SAW IN THOSE AREAS WITH EXISTING NATIVE TREE SPECIES THAT ARE TO BE PRESERVED. THESE PLANTS MAY BE CUT NEAR THE GROUND AND THE MATERIAL LESS THAN TWO INCHES DIAMETER MAY BE REMOVED FROM THE AREA AND DISPOSED OF APPROPRIATELY. ALL MATERIAL FROM THESE NOXIOUS, INVASIVE, AND NON-NATIVE PLANTS GREATER THAN TWO (2) INCHES DIAMETER SHALL BE CUT TO ALLOW CONTACT WITH THE GROUND, THUS ENCOURAGING DECOMPOSITION. IN AREAS WHERE NO NATIVE SPECIES ARE PRESENT GRADING MAY BE DONE TO REMOVE THE INVASIVE SPECIES TO BE FOLLOWED BY TREE PLANTING. THE USE OF BROADCAST SPRAYING OF HERBICIDES IS NOT PERMITTED. HOWEVER, THE USE OF HERBICIDES TO DISCOURAGE RE-SPROUTING OF INVASIVE. NOXIOUS OR NON-NATIVE PLANTS IS PERMITTED IF DONE AS AN APPLICATION OF THE CHEMICAL DIRECTLY TO THE CUT STUMP IMMEDIATELY FOLLOWING CUTTING OF PLANT TOPS. THE USE OF ANY HERBICIDE SHALL BE DONE IN ACCORDANCE WITH THE LABEL INSTRUCTIONS AND BE APPLIED BY A CERTIFIED PESTICIDE





5. MOUND SOIL ONLY WITHIN LIMITS OF DISTURBANCE.

PROTECTIVE SIGNAGE IS REQUIRED. 7 ALL STANDARD MAINTENANCE FOR SEDIMENT CONTROL DEVICES APPLY TO THESE DETAILS.

PRIOR TO CONSTRUCTION AND REMOVED BEFORE


THE INSTALLATION OF THE SPLIT RAIL FENCE)

TREE SAVE / SILT FENCE NOT TO SCALE INOTE: FENCING TO BE INSTALLED


TASKS MONTHS TRANSPLANT OF 2 DBH OR GREATER SEEDLINGS. WHIPS MONITORING RTILIZER (IF NEEDED)+ RECOMMENDED, OPTIMAL TIME RECOMMENDED WITH ADDITIONAL CARE RECOMMENDED


DEPENDENT UPON SITE CONDITIONS: WEEKLY WATERING IS STRONGLY RECOMMENDED FROM MAY THROUGH OCTOBER UNLESS WEEKLY RAINFALL EQUALS 1" ACTIVITIES DURING NOVEMBER THROUGH FEBRUARY DEPEND ON GROUND CONDITIONS NO FALL PLANTING OF DAKS AND PINES THE PLANTING AND CARE OF TREES IS MOST SUCCESSFUL WHEN COORDINATED WITH THE LOCAL CONDITIONS IS CALENDAR SUMMARIZES SOME OF THE RECOMMENDED TIME FRAMES FOR BASIC REFORESTATION AND STRESS REDUCTION ACTIVITIES


TREE PLANTING AND MAINTENANCE CALENDAR





PRUNING A BRANCH LIVING BRANCH DEAD BRANCH ---BRANCH COLLAR HARDWOODS CONIFERS - FOR LIVING OR DEAD BRANCH NOTES: 1. REMOVE BRANCH WEIGHT BY UNDERCUTTING AT 'A' AND REMOVE LIMB BY CUTTING THROUGH AT 'AB' REMOVE STUB AT 'CD'. (LINE BETWEEN BRANCH BARK RIDGE AND OUTER EDGE OF BRANCH COLLARI 3. IF 'D' IS DIFFICULT TO FIND ON HARDWOODS, ANGLE OF 'CD' TO TRUNK SHOULD. 4. BE THE REFLECTIVE ANGLE OF THE BARK BRANCH RIDGE TO THE TRUNK S. ONLY PRUNE AT SPECIFIED TIMES. REMOVE NO MORE THAN 30% OF CROWN AT ONE TIME PRUNING A LEADER TO REDUCE SIZE LATERAL BRANCH REMOVE TOP WEIGHT BY UNDERCUTTING AT 'A' AND REMOVE LIMB BY CUTTING THROUGH 'AB'. REMOVE STUB AT "EF" PARALLEL TO THE BARK BRANCH RIDGE . ONLY PRUNE AT SPECIFIED TIMES . NO MORE THAN 30% OF CROWN TO BE REMOVED AT ONE TIME DIAMETER OF LATERAL BRANCH SHOULD BE NO LESS THAN 30% OF THE DIAMETER TREE PRUNING











REFORESTATION/AFFORESTATION AND PERMANENT TREE SAVE

Nonrandom Positive Association SPECIES 1 (SPECIES 2 Naturally obsurring populations of trees tend to be found in informal groupings. A cluster of trees is really a mosaic of different species groups. The objective of an afforestation/referestation plan is to select the appropriate species and distribution pattern for a chose site that mimic natural ource: Prince Georgee County Wondland Conservation Manual Aggregate Distribution Drift taper or feather out along the edges. Clusters often appear as elongated or lear Mixing Transplant Stock Locate larger trees (B&B or container grown) or transplant stock at the perimeter of reforesistion/afforestation plantings of whites, seeding grown stock. — Protective Fencing ಕ್ಟ Smaller Stock Sassos: Adapted from Forest Conservation Manual, 1991 Planting Distribution Patterns Figure A:19

Typical Forest Tree Distribution Patterns

WOODLAND CONSERVATION AREA MANAGEMENT NOTES

Prepared by the Environmental Planning Section, Planning Department, M-NCPPC

hazardous may be removed.

Removal of Hazardous Trees or Hazardous Limbs By Developers or Builders The developer and/or builder is responsible for the complete preservation of all forested areas shown on the approved plan to remain undisturbed. Only trees or parts thereof designated by the Department of Environmental Resources as dead, dying, or

 A tree is considered hazardous if a condition is present which leads a Licensed Arborist or a Licensed Tree Expert to believe that the tree or a portion of the tree has a potential to fall and strike a structure, parking area, or other high use area and result in personal injury or property damage

If a hazardous condition may be alleviated by corrective pruning, the Licensed Arborist or a Licensed Tree Expert may proceed without further authorization. The pruning must be done in accordance with the latest edition of the ANSI A-300 Pruning Standards (ATree, Shrub, and Other Woody Plant Maintenance - Standard Practices@).

Corrective measures requiring the removal of the hazardous tree or portions thereof shall require authorization by the building or grading inspector if there is a valid grading or building permit for the subject lots or parcels on which the trees are located. Only after approval of the appropriate inspector may the tree be cut by chainsaw to near the existing ground level. The stump may not be removed or covered with soil, mulch or other materials that would inhibit sprouting.

4. Debris from the tree removal or pruning that occurs within 35 feet of the woodland edge may be removed and properly disposed of by recycling, chipping or other acceptable methods. All debris that is more than 35 feet from the woodland edge shall be cut up to allow contact with the ground, thus encouraging decomposition. The smaller materials shall be placed into brush piles that will serve as

Removal of Hazardous Trees, Hazardous Limbs, Noxious Plants, Invasive Plants or Non-Native Plants in Woodland Conservation Areas Owned by Individual Homeowners

1. If the developer or builder no longer has an interest in the property the home owner shall obtain a written statement from the Licensed Arborist or Licensed Tree Expert identifying the hazardous condition and the proposed corrective measures prior to having the work conducted. The tree may then be removed by the arborist or tree expert. The stump shall be cut as close to the ground as possible and left in place. The removal or grinding of the stumps in the woodland conservation area is not permitted.

The removal of noxious, invasive, and non-natives plant species from the woodland conservation areas may be done with the use of hand-held equipment only such as pruners or a chain saw. These plants may be cut near the ground and the material less than two inches diameter may be removed from the area and disposed of appropriately. All material from these noxious, invasive, and non-native plants greater than two (2) inches diameter shall be cut to allow contact with the ground, thus encouraging decomposition. 3. The use of broadcast spraying of herbicides is not permitted. However, the use of herbicides to discourage re-sprouting of invasive, noxious, or non-native plants is permitted if done as an application of the chemical directly to the cut stump immediately following cutting of plant tops. The use of any herbicide shall be done in accordance with the label instructions.

Note: The use of chainsaws is extremely dangerous and should not be conducted with poorly maintained equipment, without safety equipment, or by individuals not trained in the use of this equipment for the pruning and/or cutting of trees.

Protection of Reforestation and Afforestation Areas by Developers or Builders

1. Reforestation and afforestation areas shall be planted prior to the occupancy of the nearest building or residence. If planting cannot occur due to planting conditions, the developer or property owner shall install the fencing and signage in accordance with the approved Type II Tree Conservation Plan. Planting shall then be accomplished during the next planting season. If planting is delayed beyond the transfer of the property title, to the homeowner, the developer shall obtain a signed statement from the purchaser indicating that they understand that the reforestation area is located on their property and that reforestation will occur during the next planting season. A copy of that document shall be presented to the Grading Inspector and the Environmental Planning Section.

Reforestation areas shall not to be mowed, however, the management of competing vegetation around individual trees is acceptable.

Protection of Reforestation and Afforestation Areas by Individual Homeowners 1. Reforestation fencing and signage shall remain in place in accordance with the approved Type II Tree Conservation Plan or until the trees have grown sufficiently to have crown

Reforestation areas shall not to be moved, however, the management of competing vegetation around individual trees is acceptable.

Woodland Areas NOT Counted as Part of the Woodland Conservation Requirements

1. A revised Tree Conservation Plan is required prior to clearing any woodland area which is not specifically identified to be cleared on the most recently approved Type II Tree Conservation (TCP) on file in the office of the M-NCPPC, Environmental Planning Section located on the 4th flood of the County Administration Building at 14741 Governor Oden Bowie Drive, Upper Marlboro, Maryland 20772, phone 301–952–3650.

Additional mitigation will be required for the clearing of all woodlands beyond that Additional mitigation will be required for the clearing of all woodlands beyond that reflected on the approved plans. Although clearing may be allowed, it may be subject to additional replacement requirements, mitigation, and fees which must be reflected on TCP revisions approved by the M-NCPPC Environmental Planning Section.

2 Homeowners or property owners may remove trees less than two (2) inches diameter, shrubs, and vines in woodland areas which are saved but not part of the Woodland Conservation requirements after all permits have been released for the subject property. This area may not be tilled or have other ground disturbances which would result in damage to the tree roots. Raking the leaves and overseeding with native grasses, native flowers or native ground covers is acceptable. Seeding with invasive grasses including any variety of Kentucky 31 fescue is not acceptable.

> 5 YEAR MANAGEMENT PLAN FOR RE/AFFORESTATION field check the re-afforestation area according to the following schedule:

Site Preparation and Tree Planting <u>Survival check</u> ance annually (September-November, see Note 1) <u>Matering if needed</u> (2 x month) Control of undesirable vegetation as needed (1 \times in June # 1 x in September min.)

Year 2-3: <u>Reinforcement planting If needed</u> (see Note 2) <u>Survival check</u> once annually (September-November) Control of undesirable vegetation if needed (1 x in May \$

Year 4-5: Reinforcement planting If needed (See Note 2) <u>Survival check</u> once annually (September-November)

1) Survival Check: Check planted stock against plant list (or as-built) by walking the site and taking inventory. Plants must show Vitality. Submit field data forms (Condition Check Sheets) to owner after each inspection. Remove all dead plants. 2) Reinforcement Planting: Replace dead or missing plants in

sufficient quantity to bring the total number of live plants to at least 75% of the number originally planted. If a particular species suffers unusually high mortality, replace with an alternate plant

3) Miscellaneous: Fertilization or watering during years i through 3 will be done on an as needed basis. Special return operations or recommendations will be conducted on an as needed basis. Remove perimeter fencing and signage after year 5 based on the

BY MARK SOMERVILLE, PRESIDENT

Property Owners Awareness Certificate / We COLLINGBROOK DEVELOPMENT, LLC hereby acknowledge that we are aware of this Type 2 Free Conservation Plan (TCP2) and the we understand the requirements as set forth in this TCP2. COLLINGBROOK DEVELOPMENT, LLC BY CARUSO HOMES, INC. AUTHORIZE SIGNATURE

Prince George's County Planning Department, M-NCPPC Environmental Planning Section TREE CONSERVATION PLAN APPROVAL TCPII-037-07

#	APPROVED BY	DATE	DRD CASE
00	MEGAN K. REISER	6/30/08	
01	MEGAN K. REISER	7/3/13	
02	Magan K. Reiser	2/17/2017	staff level
03	7		otan 10 voi
0.4			

SOLTESZ

LANHAM OFFICE 4300 Forbes Boulevard, Suite 230 Engineering Lanham, MD 20706 Planning Environmental Sciences

P. 301,794,7555 F. 301,794,7656

BCG REVISE REFORESTATION ON LOTS 9 AND 34 TO ACCOMMODATE ENTRY FEATURE/SIGN EASEMENT: UPDATE CHARTS/WORKSHEET 9/14/16 Lanham 7/19/16 REVISE AFFORESTATION AREAS ON LOTS 4,5,16,33-36 AND AFFORESTATION TO NATURAL REGERATION WHERE CURRENTLY PRESENT. Waldorf BCG 12/19/14 Leonardtown REVISION TO REMOVE LOT 30 AFFORESTATION AND ADD TO LOTS 8,9,10,25,26,28& 29 REVISION TO ADDRESS 11/6/12 MNCPPC COMMENTS 5/15/13 KVC REVISION TO ADDRESS MNCPPC COMMENTS DATED 9/27/12 10/24/12 REVISION TO ADD PHASE 2 7/20/12 CAD STANDARDS VERSION: V8 - 2000 www.solteszco.com CHECKED: XVI

MISS UTILITY NOTE

INFORMATION CONCERNING EXISTING UNDERGROUND UTILITIE WAS OBTAINED FROM AVAILABLE RECORDS. THE CONTRACTOR MUST DETERMINE THE EXACT LOCATION AND ELEVATION OF AL EXISTING UTILITIES AND UTILITY CROSSINGS BY DIGGING TES PITS BY HAND, WELL IN ADVANCE OF THE START OF EXCAVATION CONTACT "MISS UTILITY" AT 1-800-257-7777, 48 HOURS PRIOR T THE START OF EXCAVATION. IF CLEARANCES ARE LESS THAN SHOWN ON THIS PLAN OR TWELVE (12) INCHES, WHICHEVER IS LESS, CONTACT THE ENGINEER AND THE UTILITY COMPANY BEFORE PROCEEDING WITH CONSTRUCTION. CLEARANCES LESS THAN NOTED MAY REQUIRE REVISIONS TO THIS PLAN.

CARUSO HOMES, INC. 1655 CROFTON BLVD. SUITE 200 CROFTON, MARYLAND 21114 301-261-0277 301-576-3923 (FAX) CONTACT: MARK SOMERVILLE

OWNER/DEVELOPER/APPLICANT





REFORESTATION INSPECTION AND PLANTING NARRATIVE

A. THE FIRST INSPECTION SHALL OCCURE AFTER FLAGGING/ STAKING OF THE L.O.D. AND /OR STREAM BUFFERS, AND PRIOR TO ANY ELEARING, GRADING OR SEDIMENT CONTROL MEASURES. THIS INSPECTION IS TO ADDRESS THE ISSUES OF TREE PROTECTION AND SEDIMENT CONTROL. THE DEVELOPER AND REPRESENTATIVES FROM M-NCPPC AND DPW&T WILL MEET TO WALK THE PROPOSED DEVELOPED AND REPRESENTATIVES FROM M-NCPPC AND ADDRESS TO WALK THE PROPOSED DEVELOPED TO WALK THE PROPOSED AND REPRESENTATIVES AND DESTRUMENT THE STATE AND DEVELOPED AND ADDRESS THE STATE AND DEVELOPED AN

LIMITS OF DISTURBANCE AND DETERMINE THE FINAL LOCATIONS OF SEDIMENT CONTROL DEVICES AND

B. THE SECOND INSPECTION SHALL OCCUR AFTER PLACEMENT OF SEDIMENT CONTROL DEVICES AND NOTE: TREE PROTECTION DEVICES, AND PRIOR TO CLEARING AND GRADING. THIS INSPECTION IS TO DETERMINE THE COMPLETION AND ADEQUACY OF PROTECTIVE MEASURES.

C. THE THIRD INSPECTION SHALL OCCUR PRIOR TO PLANTING IN REFORESTATION AREAS. THIS PRE-PLANTING INSPECTION IS TO MAKE FINAL DECISIONS REGARDING THE BEST IMPLEMENTATION

D. THE FOURTH INSPECTION SHALL OCCUR IMMEDIATELY FOLLOWING THE COMPLETION OF THE REFORESTATION PLANTING. THIS INSPECTION IS TO DETERMINE THE COMPLETION AND ADEQUACY

E. THE FIFTH AND FINAL INSPECTION SHALL OCCUR AT THE COMPLETION OF THE TWO-YEAR MAINTENANCE PROGRAM. THE PURPOSE OF THIS INSPECTION IS TO DETERMINE THE SUCCESS AND ADEQUACY OF THE MAINTENANCE PROGRAM (AND DEER MANAGEMENT PROGRAM). A FINAL DETERMINATION WILL BE MADE AT THIS TIME AS TO WHETHER ADDITIONAL PLANTINGS AND A FURTHER MAINTENANCE PROGRAM ARE NECESSARY.

A. IN AREAS WITH SUBSTANTIAL GROWTH OF INVASIVE GROUNDCOVER SPECIES, MEASURES SHALL BE TAKEN TO REMOVE AND CONTROL INVASIVES. THE INFESTED AREAS SHOULD BE MOWN PRIOR TO COMMENCEMENT OF PLANTING. NEGESSARY WEED CONTROL MEASURES SHOULD BE DETERMINED DURING THE PRE-PLANTING INSPECTION, INCLUDING, BUT NOT LIMITED TO, MULCHING, PERIODIC MOWING AROUND THE REFORESTATION PLANTINGS, AND FABRIC COVERINGS. THE USE OF CHEMICAL WEED CONTROLS WILL BE LIMITED TO EXTREME CASES AND, AND ONLY WITH PRIOR WRITTEN APPROVAL BY MNCPPC STAFF. WHERE PERIODIC MOWING WILL OCCUR AS A WEED CONTROL MEASURE, THE TYPICAL TREE PLANTING DISTRIBUTION PATTERN SHOULD BE MODIFIED SO AS TO ALLOW ACCESS BY MOWING EQUIPMENT WITHOUT DAMAGE TO PLANTINGS.

A. A SOILS ANALYSIS WILL BE CONDUCTED PRIOR TO COMMENCEMENT OF REFORESTATION. ON LAND WHERE EXTENSIVE AGRICULTURAL USE HAS OCCURRED IN THE PAST, TEST PITS WILL BE DUG IN AREAS OF UNDISTURBED SOIL TO DETERMINE IF A FRAGIPAN LAYER IS PRESENT. IF FRAGIPAN IS PRESENT, IT SHOULD BE PIERCED BY AUGURING AND PLANTING HOLES

B. SOILS SHOULD BE TREATED BY INCORPORATING NATURAL MULCH WITHIN THE TOP 12 INCHES, OR AMENDMENTS AS DETERMINED BY THE SOILS ANALYSIS. NATURAL AMENDMENTS, SUCH AS ORGANIC MULCH OR LEAF MOLD COMPOST ARE PREFERRED.

C. IF FILL MATERIAL IS USED AT THE PLANTING SITE, IT SHOULD BE CLEAN FILL WITH 12 INCHES OF NATIVE SOIL. STOCKPILING OF NATIVE TOP SOILS MUST BE DONE IN SUCH A WAY THAT THE HEIGHT OF THE PILE DOES NOT DAMAGE THE SEED BANK.

IT IS RECOMMENDED THAT PLANTING OCCUR WITHIN 24 HOURS OF DELIVERY TO THE SITE, PLANT MATERIALS WHICH ARE LEFT UNPLANTED FOR MORE THAN 24 HOURS SHOULD BE PROTECTED FROM DIRECT SUN AND WEATHER AND KEPT MOIST. NURSERY STOCK SHOULD NOT BE LEFT UNPLANTED FOR MORE

PRIOR TO PLANTING, PLANTING STOCK SHOULD BE INSPECTED. PLANTS NOT CONFORMING TO STANDARD NURSERYMAN SPECIFICATIONS FOR SIZE, FORM, VIGOR, ROOTS, TRUNK WOUNDS, INSECTS, AND DISEASE

A. CONTAINER GROWN STOCK: SUCCESSFUL PLANTING OF CONTAINER GROWN STOCK REQUIRES CAREFUL SITE PREPARATION AND INSPECTION OF THE PLANT MATERIAL ROOT SYSTEM, CAUTION

CAREFUL SITE PREPARATION AND INSPECTION OF THE PLANT MATERIAL ROOT SYSTEM. CAUTION IS RECOMMENDED WHEN SELECTING PLANTS GROWN IN A SOILS MEDIUM DIFFERING FROM THAT OF THE PLANTING SITE. THE PLANT SHOULD BE REMOVED FROM THE CONTAINER AND THE ROOTS GENTLY LOOSENED FROM THE SOILS. IF THE ROOTS ENCIRCLE THE ROOT BALL, SUBSTITUTION IS STRONGLY RECOMMENDED. 1-SHAPED OR KINKED ROOT SYSTEMS SHOULD ALSO BE NOTED, AND SUBSTITUTED IF NECESSARY. ROOTS MAY NOT BE TRIMMED ON-SITE, DUE TO THE INCREASED CHANCES OF SOIL BORNE DISEASES. THE PLANTING FIELD SHOULD BE PREPARED AS SPECIFIED. NATIVE STOCKPILED SOILS SHOULD BE USED TO BACKFILL PLANTING FIELD. RAKE SOILS EVENLY OVER THE PLANTING FIELD AND COVER WITH 2 TO 4 INCHES OF MULCH.

BOTH PRACTICES WILL TEND TO SEPARATE THE TRUNK FROM THE ROOT BALL. PRIOR TO PLANTING, ROOT BALLS SHOULD BE KEFT MOIST.

B. BALLED AND BURLAPPED TREES: BALLED AND BURLAPPED TREES MUST BE HANDLED WITH CARE WHILE PLANTING. TREES SHOULD NOT BE PICKED UP BY THE TRUNK OR DROPPED, AS

SHOULD BE DUG TO TWICE THE NORMAL DIAMETER FOR THE MATERIAL PLANTED.

OF THE PLANTING PLAN, INCLUDING, BUT NOT LIMITED TO, THE FINAL PLACEMENT AND SELECTION OF PLANT SPECIES, DETERMINATION OF THE REGENERATION POTENTIAL OF EXISTING PLANTS TO REMAIN, AND A DETERMINATION OF THE BEST EDGE PLANTING TREATMENT. THE PURCHASE AND DELIVERY OF PLANT MATERIALS SHOULD NOT BE MADE UNTIL AFTER THIS INSPECTION SINCE A DETERMINATION MAY BE MADE IN THE FIELD TO ALTER THE CHOICE OF PLANT MATERIAL.

1. REFORESTATION INSPECTION SCHEDULE

TREE PROTECTION DEVICES

2. PRE-PLANTING CONSIDERATIONS

3. PLANT MATERIAL STORAGE

4. ON-SITE INSPECTION

SHOULD BE REPLACED.

5. PLANTING SPECIFICATIONS

THERE SHALL BE FIVE INSPECTIONS FOR FOREST CONSERVATION


TREE CONSERVATION PLAN TYPE 2 PHASE II

PROJECT NO.

RODENHAUSER PROPERTY

BOWIE (14th) ELECTION DISTRICT, PRINCE GEORGE'S COUNTY, MARYLAND

P:\05221000\ENGINEER\ENV\TCPII_Ph2_05.sht Scale= 50.0000 ft / in. User= bgillette PLTdrv= PDF_Color_150.pltcfg Pentbl= TEXT_SUB.tbl 1/18/2017 1:12:30 Pl



TECHNICIAN: YOR

CHECKED: XVI

BOWIE (14th) ELECTION DISTRICT, PRINCE GEORGE'S COUNTY, MARYLAND P:\05221000\ENGINEER\ENV\TCPII_Ph2_06.sht Scale= 50.0000 ft / in. User= bgillette PLTdrv= PDF_Color_150.pltcfg Pentbl= TEXT_SUB.tbl 1/18/2017 1:14:01 PM