

EXPIRES AND IS NO LONGER VALID. 2. CUTTING OR CLEARING OF WOODLAND NOT IN CONFORMANCE WITH THIS PLAN OR WITHOUT THE EXPRESSED WRITTEN CONSENT OF THE PLANNING

DIRECTOR OR DESIGNEE SHALL BE SUBJECT TO A \$1.50 PER SQUARE FOOT MITIGATION FEE.

3. A PRE-CONSTRUCTION MEETING IS REQUIRED PRIOR TO THE ISSUANCE OF GRADING PERMITS. THE DEPARTMENT OF PUBLIC WORKS AND TRANSPORTATION OR THE DEPARTMENT OF ENVIRONMENTAL RESOURCES, AS APPROPRIATE, SHALL BE CONTACTED PRIOR TO THE START OF ANY WORK ON THE SITE TO CONDUCT A PRE-CONSTRUCTION MEETING WHERE IMPLEMENTATION OF WOODLAND CONSERVATION MEASURES SHOWN ON THIS PLAN WILL BE DISCUSSED

THROUGH THE PROVISION OF A COPY OF THIS PLAN AT TIME OF CONTRACT SIGNING. FUTURE PROPERTY OWNERS ARE ALSO SUBJECT TO THIS

4. THE DEVELOPER OR BUILDER OF THE LOTS OR PARCELS SHOWN ON THIS PLAN SHALL NOTIFY FUTURE BUYERS OF ANY WOODLAND CONSERVATION AREAS

5. THE OWNERS OF THE PROPERTY SUBJECT TO THIS TREE CONSERVATION PLAN ARE SOLELY RESPONSIBLE FOR CONFORMANCE TO THE REQUIREMENTS CONTAINED HEREIN.

6. THE PROPERTY IS WITHIN THE DEVELOPING TIER AND IS ZONED M-X-T.

7. THE SITE IS NOT ADJACENT TO A ROADWAY DESIGNATED AS SCENIC, HISTORIC, A PARKWAY OR SCENIC BYWAY.

8. THE SITE IS ADJACENT TO CAMPUS WAY NORTH WHICH IS CLASSIFIED AS AN URBAN ARTERIAL ROAD. 9. THIS PLAN IS GRANDFATHERED UNDER CB-27-2010, SECTION 25-117(G).

POST DEVELOPMENT NOTES WHEN WOODLANDS AND/OR SPECIMEN, HISTORIC OR CHAMPION TREES ARE TO REMAIN:

1. IF THE DEVELOPER OR BUILDER NO LONGER HAS AN INTEREST IN THE PROPERTY AND THE NEW OWNER DESIRES TO REMOVE A HAZARDOUS TREE OR PORTION THEREOF, THE NEW OWNER SHALL OBTAIN A WRITTEN STATEMENT FROM A CERTIFIED ARBORIST OR LICENSED TREE EXPERT IDENTIFYING THE HAZARDOUS CONDITION AND THE PROPOSED CORRECTIVE MEASURES PRIOR TO HAVING THE WORK CONDUCTED. AFTER PROPER DOCUMENTATION HAS BEEN COMPLETED PER THE HANDOUT "GUIDANCE FOR PRINCE GEORGE'S COUNTY PROPERTY OWNERS, PRESERVATION OF WOODLAND CONSERVATION AREAS", THE ARBORIST OR TREE EXPERT MAY THEN REMOVE THE TREE. THE STUMP SHALL BE CUT AS CLOSE TO THE GROUND AS POSSIBLE AND LEFT IN PLACE. THE REMOVAL OR GRINDING OF THE STUMPS IN THE WOODLAND CONSERVATION AREA IS NOT PERMITTED.

IF A TREE OR PORTIONS THEREOF ARE IN IMMINENT DANGER OF STRIKING A STRUCTURE, PARKING AREA OR OTHER HIGH USE AREA AND MAY RESULT IN PERSONAL INJURY OR PROPERTY DAMAGE THEN THE CERTIFICATION IS NOT REQUIRED AND THE PERMITEE SHALL TAKE CORRECTIVE ACTION IMMEDIATELY. THE CONDITION OF THE AREA SHALL BE FULLY DOCUMENTED THROUGH PHOTOGRAPHS PRIOR TO CORRECTIVE ACTION BEING TAKEN. THE PHOTOS SHALL BE SUBMITTED TO THE INSPECTOR FOR DOCUMENTATION OF THE DAMAGE.

TREE WORK TO BE COMPLETED WITHIN A ROAD RIGHT-OF-WAY REQUIRES A PERMIT FROM THE MARYLAND DEPARTMENT OF NATURAL RESOURCES UNLESS THE TREE REMOVAL IS SHOWN WITHIN THE APPROVED LIMITS OF DISTURBANCE ON A TCP2. THE WORK IS REQUIRED TO BE CONDUCTED BY A LICENSED

2. THE REMOVAL OF NOXIOUS, INVASIVE, AND NON-NATIVE PLANT SPECIES FROM ANY WOODLAND PRESERVATION AREA SHALL BE DONE WITH THE USE OF HAND-HELD EQUIPMENT ONLY (PRUNERS OR A CHAIN SAW). THESE PLANTS MAY BE CUT NEAR THE GROUND AND MATERIAL LESS THAN TWO INCHES DIAMETER MAY BE REMOVED FROM THE AREA AND DISPOSED OF APPROPRIATELY. ALL MATERIAL FROM THESE NOXIOUS, INVASIVE, AND NON-NATIVE PLANTS GREATER THAN TWO (2) INCHES DIAMETER SHALL BE CUT TO ALLOW CONTACT WITH THE GROUND, THUS ENCOURAGING DECOMPOSITION.

3. THE USE OF BROADCAST SPRAYING OF HERBICIDES IS NOT PERMITTED. HOWEVER, THE USE OF HERBICIDES TO DISCOURAGE RE-SPROUTING OF INVASIVE NOXIOUS, OR NON-NATIVE PLANTS IS PERMITTED IF DONE AS AN APPLICATION OF THE CHEMICAL DIRECTLY TO THE CUT STUMP IMMEDIATELY FOLLOWING

CUTTING OF PLANT TOPS. THE USE OF ANY HERBICIDES SHALL BE DONE IN ACCORDANCE WITH THE LABLEL INSTRUCTIONS. 4. THE USE OF CHAINSAWS IS EXTREMELY DANGEROUS AND SHOULD NOT BE CONDUCTED WITH POORLY MAINTAINED EQUIPMENT, WITHOUT SAFETY EQUIPMENT, OR BY INDIVIDUALS NOT TRAINED IN THE USE OF THIS EQUIPMENT FOR THE PRUNING AND/OR CUTTING OF TREES.

SPECIMEN TREE #222 5-YEAR MAINTENANCE SCHEDULE

ALL MAINTENANCE WORK SHALL BE CONDUCTED BY OR UNDER THE SUPERVISION OF AN ISA CERTIFIED ARBORIST OR MARYLAND LICENSED TREE PROFESSIONAL.

ALL CONSTRUCTION EQUIPMENT SHALL BE KEPT OUTSIDE OF THE TREE PROTECTION FENCE.

AN ANNUAL INSPECTION REPORT SHALL BE SUBMITTED TO THE ENVIRONMENTAL PLANNING SECTION BY NOVEMBER 1ST OF EACH YEAR BEGINNING IN 2014 TO ENSURE THAT THE FOLLOWING MAINTENANCE SCHEDULE IS BEING FOLLOWED.

YEAR 0-1: PRE-CONSTRUCTION

1. THE CRITICAL ROOT ZONE (CRZ) SHALL BE DETERMINED BY INVESTIGATIVE DIGGING WITH THE FOLLOWING FORMULA AS A STARTING POINT: RADIUS = 1.5'* DBH, WHERE DBH STANDS FOR DIAMETER AT BREAST HEIGHT.

MARK THE LOCATION OF THE TREE PROTECTION FENCE. FENCE LOCATION SHALL BE WITHIN 1' OF THE CRITICAL ROOT ZONE. PROVIDE AN ACCESS POINT IN THE FENCE. ENSURE THAT NO MORE THAN 25% OF THE ROOTS SHALL BE IMPACTED.

REMOVE ALL TRASH AND DEBRIS BY HAND FROM WITHIN THE CRZ OR DRIP LINE.

ROOT PRUNING: WHERE THE CRZ WILL BE IMPACTED BY CONSTRUCTION ACTIVITIES, PRUNE THE ROOTS USING WELL-MAINTAINED VIBRATORY PLOW FOR A CLEAN CUT PER DETAIL 5-3. ROOT PRUNING SHALL BE CONDUCTED UP TO ONE GROWING SEASON PRIOR TO CONSTRUCTION. COVER EXPOSED ROOTS IMMEDIATELY WITH TOPSOIL, PEAT MOSS, OR OTHER ORGANIC MATERIAL. MONITOR FOR SIGNS OF STRESS AND APPLY WATER IF NEEDED.

CROWN REDUCTION OR PRUNING: PRUNE ANY DEAD, DAMAGED OR DISEASED LIMBS. PRUNING SHALL OCCUR IN LATE WINTER, EARLY SPRING, OR MID-SUMMER. NO MORE THAN 1/3 OF THE CROWN SHALL BE REMOVED AT ANY TIME. MONITOR FOR SIGNS OF STRESS.

WATERING: PROVIDE WATERING AS NEEDED, IF TREE IS STRESSED OR DROUGHT CONDITIONS ARE PRESENT

FERTILIZATION: USE LOW NITROGEN AND SLOW RELEASE FERTILIZERS AND APPLY IN LATE FALL OR EARLY SPRING. AVOID ROOT INJURY WHILE INJECTING FERTILIZER. DO NOT APPLY FERTILIZER CLOSER THAN 3' TO THE TREE TRUNK. PROVIDE VERTICAL MULCHING.

YEAR 1-4 (OR DURATION OF CONSTRUCTION):

MONITOR THE SPECIMEN TREE EACH SEASON FOR STRESS INCLUDING SOIL COMPACTION, ROOT INJURY, TRUNK WOUNDS, LIMB INJURY, FLOOD CONDITIONS, DROUGHT CONDITION, AND INVASIVE SPECIES.

REMOVE INVASIVE SPECIES AND PROVIDE ADDITIONAL SOIL AERATION, ROOT PRUNING, CROWN PRUNING, WATERING AND FERTILIZATION AS NECESSARY

3. REMOVE ANY ACCUMULATED TRASH OR DEBRIS FROM WITHIN THE CRZ OR DRIP LINE

YEAR 4-5 (OR POST-CONSTRUCTION):

CONSTRUCTION ACTIVITY.

ENSURE STRESS REDUCTION BY PROVIDING ANY ADDITIONAL SOIL AERATION, ROOT PRUNING, CROWN PRUNING, WATERING AND FERTILIZATION IN

REPAIR ANY TREE DAMAGE INCLUDING ROOT REPAIR, REMOVAL OF DEAD LIMBS AND SOIL AERATION. DEAD LIMBS SHALL BE REMOVED CAREFULLY TO IMPROVE AESTHETICS AND THOSE LIMBS WILL BE RIGGED DOWN BY ROPE SYSTEM OR CRANE.

REMOVE TREE PROTECTION DEVICES.

*PREPARED BY DEWBERRY CONSULTANTS AND REVIEWED BY MR. WILLIAM DOWLING, MTEL #001146

FIVE-YEAR MANAGEMENT PLAN FOR RE/AFFORESTATION AREAS

FIELD CHECK THE RE-AFFORESTATION AREA ACCORDING TO THE FOLLOWING SCHEDULE:

SITE PREPARATION AND TREE PLANTING

SURVIVAL CHECK ONCE ANNUALLY (SEPTEMBER-NOVEMBER) SEE NOTE 1 WATERING IS NEEDED (2 X MONTH) CONTROL OF UNDESIRABLE VEGETATION AS NEEDED (1 X IN JUNE AND 1 X IN SEPTEMBER MIN.)

REINFORCEMENT PLANTING IS NEEDED (SEE NOTE 2) SURVIVAL CHECK ONCE ANNUALLY (SEPTEMBER-NOVEMBER)

CONTROL OF UNDESIRABLE VEGETATION IF NEEDED (1 X IN MAY AND 1 X IN AUGUST MIN.)

REINFORCEMENT PLANTING IF NEEDED. (SEE NOTE 2) SURVIVAL CHECK (SEPTEMBER-NOVEMBER)

1. SURVIVAL CHECK: CHECK PLANTED STOCK AGAINST PLANT LIST (OR AS-BUILT) BY WALKING THE SITE AND TAKING INVENTORY. PLANTS MUST SHOW VITALITY SUBMIT FIELD DATA FORMS (CONDITION CHECK SHEETS) TO OWNER AFTER EACH INSPECTION, REMOVE ALL DEAD PLANTS.

2 REINFORCEMENT PLANTING: REPLACE DEAD OR MISSING PLANTS IN SUFFICIENT QUANTITY TO BRING THE TOTAL NUMBER OF LIVE PLANTS TO AT LEAST 75% OF THE NUMBER ORIGINALLY PLANTED. IF A PARTICULAR SPECIES SUFFERS UNUSUALLY HIGH MORTALITY, REPLACE WITH AN ALTERNATIVE PLANT TYPE. 3. MISCELLANEOUS: FERTILIZATION OR WATERING DURING YEARS 1 THROUGH 3 WILL BE DONE ON AN AS NEEDED BASIS. SPECIAL RETURN OPERATIONS OR RECOMMENDATIONS WILL BE CONDUCTED ON AN AS NEEDED BASIS. REMOVE PERIMETER FENCING AND SIGNAGE AFTER YEAR 5 BASED ON THE DATE PLANTED.

SPECIMEN TREE PRESERVATION NOTE PER CONDITION 8 OF CSP-03001

SPECIMEN TREES TO BE PRESERVED AS A PART OF THIS DSP SHALL BE PROTECTED BY A BLAZE ORANGE PLASTIC MESH FENCE AROUND THE PERIMETER OF THEIR BRANCHES. INSTALLATION OF THE BLAZE ORANGE FENCE SHALL BE IN ACCORDANCE WITH THE DETAIL PROVIDED ON SHEET 3. SPECIMEN TREES #71, 93, 202-218, 227-239, 258, AND 261-263 WITHIN 100 FEET OF THE LIMITS OF DISTURBANCE SHALL BE IDENTIFIED IN THE SPECIMEN TREE TABLE AS TO EACH TREE'S DISPOSITION BEFORE SIGNATURE APPROVAL OF THE TOPII. FENCING SHALL BE INSTALLED PRIOR TO THE START OF

REFORESTATION NOTE PER RESOLUTION 18 OF **PGCPB NO. 05-202**

THE REFORESTATION AND ASSOCIATED FENCING SHALL BE INSTALLED PRIOR TO THE ISSUANCE OF BUILDING PERMITS FOR LOTS 16-20 OF BLOCK O. A CERTIFICATION PREPARED BY A QUALIFIED PROFESSIONAL MAY BE USED TO PROVIDE VERIFICATION THAT THE REFORESTATION HAS BEEN COMPLETED. IT MUST INCLUDE, AT A MINIMUM, PHOTOS OF THE REFORESTATION AREA AND THE ASSOCIATED FENCING IN RELATION TO EACH LOT (LOTS 16-20 OF BLOCK O), WITH LABELS ON THE PHOTOS IDENTIFYING THE LOCATION AND A PLAN SHOWING THE LOCATION WHERE THE PHOTOS WERE TAKEN.

PLANTING SPECIFICATION NOTES

1. QUANTITY: (SEE PLANT SCHEDULE)

2. TYPE: (SEE PLANT SCHEDULE) 3. PLANT QUALITY STANDARDS: THE PLANTS SHALL BE HEALTHY AND STURDY REPRESENTATIVES OF THEIR SPECIES. SEEDLINGS SHALL HAVE A MINIMUM TOP GROWTH OF 18". THE DIAMETER OF THE ROOT COLLAR (THE PART OF THE ROOT JUST BELOW GROUND LEVEL) SHALL BE AT LEAST & THE ROOTS SHALL BE WELL DEVELOPED AND AT LEAST 8" LONG, NO MORE THAN TWENTY-FIVE PERCENT (25%) OF THE ROOT SYSTEM (BOTH PRIMARY AND AUXILIARY/FIBROUS ROOTS SHALL BE PRESENT.

PLANTS THAT DO NOT HAVE AN ABUNDANCE OF WELL DEVELOPED TERMINAL BUDS ON THE LEADERS AND BRANCHES SHALL BE REJECTED.

PLANTS SHALL BE SHIPPED BY THE NURSERY IMMEDIATELY AFTER LIFTING FROM THE FIELD OR REMOVAL FROM THE GREEN HOUSE, AND PLANTED IMMEDIATELY UPON RECEIPT BY THE LANDSCAPE CONTRACTOR.

IF THE PLANTS CANNOT BE PLANTED IMMEDIATELY AFTER DELIVERY TO THE REFORESTATION SITE, THEY SHALL BE STORED IN THE SHADE WITH THEIR ROOT MASSES PROTECTED FROM DIRECT EXPOSURE TO SUN AND WIND BY THE USE OF STRAW, PEAT MOSS, COMPOST, OR OTHER SUITABLE MATERIAL AND SHALL BE MAINTAINED THROUGH PERIODIC WATERING, UNTIL THE TIME OF PLANTING.

4. PLANT HANDLING: THE QUANTITY OF SEEDLINGS TAKEN TO THE FIELD SHALL NOT EXCEED THE QUANTITY THAT CAN BE PLANTED IN A DAY. SEEDLINGS, ONCE REMOVED FROM THE NURSERY OR TEMPORARY STORAGE AREA SHALL BE PLANTED IMMEDIATELY.

5. TIMING OF PLANTING: THE BEST TIME TO PLAN SEEDLINGS IS WHILE THEY ARE DORMANT, PRIOR TO SPRING BUDDING. THE MOST SUITABLE MONTHS FOR PLANTING ARE MARCH AND APRIL, WHEN THE SOIL IS MOIST, BUT MAY BE PLANTED FROM MARCH THROUGH NOVEMBER. NO PLANTING SHALL BE DONE WHILE GROUND IS FROZEN. PLANTING SHALL OCCUR WITHIN ONE GROWING SEASON OF THE ISSUANCE OF GRADING/BUILDING PERMITS AND/OR REACHING THE FINAL GRADES AND STABILIZATION OF PLANTING AREAS.

6. SEEDLING PLANTING: TREE SEEDLINGS SHALL BE PLANTED USING A DIBBLE BAR OR SHARP-SHOOTER SHOVEL. IT IS IMPORTANT THAT THE SEEDLING BE PLACED IN THE HOLE SO THAT THE ROOTS CAN SPREAD OUT NATURALLY; THEY SHOULD NOT BE TWISTED, BALLED UP OR BENT. MOIST SOIL SHOULD THEN BE PACKED FIRMLY AROUND THE ROOTS. SEEDLINGS SHOULD BE PLANTED AT A DEPTH WHERE THEIR ROOTS LIE JUST BELOW THE GROUND SURFACE. AIR POCKETS SHOULD NOT BE LEFT AFTER CLOSING THE HOLE WHICH WOULD ALLOW THE ROOTS TO DRY OUT. SEE PLANTING DETAILS FOR FURTHER EXPLANATION. IF THE CONTRACTOR WISHES TO PLANT BY ANOTHER METHOD, THE PREPARER OF THIS TREE CONSERVATION PLAN MUST BE CONTACTED AND GIVE HIS APPROVAL BEFORE PLANTING MAY BEGIN.

7. SPACING: SEE PLANT SCHEDULE AND/OR PLANTING PLAN FOR SPACING REQUIREMENTS. ALSO REFER TO THE PLANTING LAYOUT DETAIL FOR A DESCRIPTION OF THE GENERAL PLANTING THEORY.

8. SOIL: UPON THE COMPLETION OF ALL GRADING OPERATIONS, A SOIL TEST SHALL BE CONDUCTED TO DETERMINE WHAT SOIL PREPARATION AND SOIL AMENDMENTS, IF ANY, ARE NECESSARY TO CREATE GOOD TREE GROWING CONDITIONS. SOIL SAMPLES SHALL BE TAKEN AT A RATE THAT PROVIDES ONE SOIL SAMPLE FOR EACH AREA THAT APPEARS TO HAVE A DIFFERENT SOIL TYPE (IF THE ENTIRE AREA APPEARS UNIFORM, THEN ONLY ONE SAMPLE IS NECESSARY), AND SUBMITTED FOR TESTING TO A PRIVATE COMPANY. THE COMPANY OF CHOICE SHALL MAKE RECOMMENDATIONS FOR IMPROVING THE EXISTING SOIL. THE SOIL WILL BE TESTED AND RECOMMENDED FOR CORRECTIONS OF SOIL TEXTURE, pH, MAGNESIUM, PHOSPHORUS, POTASSIUM, CALCIUM AND ORGANIC MATTER.

9. SOIL IMPROVEMENT MEASURES: THE SOIL SHALL THEN BE IMPROVED ACCORDING TO THE RECOMMENDATIONS MADE BY THE TESTING COMPANY. 10. FENCING AND SIGNAGE: FINAL PROTECTIVE FENCING SHALL BE PLACED ON THE VISIBLE AND/OR DEVELOPMENT SIDE OF PLANTING AREAS. THE FINAL PROTECTIVE FENCE SHALL BE INSTALLED UPON COMPLETION OF PLANTING OPERATIONS UNLESS IT WAS INSTALLED DURING THE INITIAL STAGES OF DEVELOPMENT. SIGNS SHALL BE POSTED PER THE SIGNAGE DETAIL ON THIS SHEET.

11. PLANTING METHOD: CONSULT THE PLANTING DETAIL(S) SHOWN ON THIS PLAN. 12. MULCHING: APPLY TWO-INCH THICK LAYER OF WOODCHIP OR SHREDDED HARDWOOD MUCH (AS NOTED) TO EACH PLANTING SITE (SEE DETAIL SHOWN ON

13. GROUNDCOVER ESTABLISHMENT: THE REMAINING DISTURBED AREA BETWEEN SEEDLING PLANTING SITES SHALL BE SEEDED AND STABILIZED WITH WHITE

CLOVER SEED AT THE RATE OF 5 LBS/ACRE. 14. MOWING: NO MOWING SHALL BE ALLOWED IN ANY PLANTING AREA.

15. SURVIVAL CHECK FOR BOND RELEASE: THE SEEDLING PLANTING IS TO BE CHECKED AT THE END OF EACH YEAR FOR FOUR YEARS TO ASSURE THAT NO LESS THAN 75% OF THE ORIGINAL PLANTED QUANTITY SURVIVES. IF THE MINIMUM NUMBER HAS NOT BEEN PROVIDED THE AREA MUST BE SUPPLEMENTED WITH ADDITIONAL SEEDLINGS TO REACH THE REQUIRED NUMBER AT TIME OF PLANTING.

16. SOURCE OF SEEDLINGS: TO BE DETERMINED BY APPLICANT.

INVASIVE SPECIES MANAGEMENT PLAN

SITE EVALUATION PRIOR TO CONTROL MEASURE INITIATION AND SUBSEQUENT SITE EVALUATIONS ONCE THE LIMIT OF DISTURBANCE HAS BEEN ESTABLISHED IN THE FIELD, ALL AREAS OF THE PROJECT SITE WHERE INVASIVE VEGETATIVE SPECIES CONTROL

WILL BE IMPLEMENTED SHALL BE EVALUATED BY, OR UNDER THE SUPERVISION OF, A CERTIFIED ARBORIST OR OTHER APPROPRIATELY QUALIFIED PROFESSIONAL TO DETERMINE QUANTITIES AND EXTENT OF SPECIFIC PLANT SPECIES TO BE CONTROLLED AND TO ASSIGN APPROPRIATE CONTROL MEASURES TO SITE SPECIFIC AREAS. SINCE PLANT SPECIES ARE MOST EASILY IDENTIFIED ONCE LEAF OUT HAS OCCURRED AND PRIOR TO LEAF DROP IN THE FALL, THE INITIAL SITE EVALUATION CAN TAKE PLACE AT ANY TIME DURING THE GROWING SEASON, IN CONJUNCTION WITH DETERMINATION AND MARKING OF THE LIMIT OF DISTURBANCE IN THE FIELD. HOWEVER, PER THE SPECIFIC CONTROL METHODS FOR EACH SPECIES, THERE ARE SEASONAL REQUIREMENTS FOR APPLICATION OF CONTROLS THAT WILL MAXIMIZE SUCCESSFUL IMPLEMENTATION OF CONTROL MEASURES WHICH SHOULD BE TAKEN INTO ACCOUNT WHEN THE SITE EVALUATION IS PERFORMED. THESE REQUIREMENTS SHALL BE DETERMINED BY THE QUALIFIED PROFESSIONAL AND IMPLEMENTED BY A MARYLAND LICENSED

THE SITE SHOULD BE EVALUATED TWICE MONTHLY ONCE CONTROL MEASURES HAVE BEEN INITIATED EACH GROWING SEASON, BETWEEN APRIL AND NOVEMBER OF EACH YEAR, TO MONITOR SUCCESS OF CONTROL MEASURES AND DETERMINE RECOMMENDATIONS FOR FURTHER ACTION BASED ON FIELD CONDITIONS. ALL SITE EVALUATIONS SHOULD BE PERFORMED BY, OR UNDER THE SUPERVISION OF, A CERTIFIED ARBORIST OR OTHER APPROPRIATELY QUALIFIED PROFESSIONAL. WRITTEN REPORTS OF SITE CONDITIONS FOUND DURING EACH SITE EVALUATION ALONG WITH RECOMMENDATIONS FOR FURTHER ACTION, SHOULD BE PREPARED BY THE SITE EVALUATOR WHICH SHOULD THEN BE SUBMITTED TO, REVIEWED, AND APPROVED BY AN M-NCCPC INSPECTOR.

THE USE OF BROADCAST SPRAYING OF HERBICIDES IS NOT PERMITTED. HOWEVER, THE USE OF HERBICIDES TO DISCOURAGE RE-SPROUTING OF OF INVASIVE, NOXIOUS OR NON-NATIVE PLANTS IS PERMITTED IF DONE AS AN APPLICATION OF THE CHEMICAL DIRECTLY TO THE CUT STUMP IMMEDIATELY FOLLOWING CUTTING OF PLANT TOPS OR TO THE HERBACEOUS PLANT. THE USE OF ANY HERBICIDE SHALL BE DONE IN ACCORDANCE WITH THE LABEL INSTRUCTIONS AND BE APPLIED BY A MARYLAND CERTIFIED PESTICIDE APPLICATOR.

PROPOSED MAINTENANCE PLAN

MAINTENANCE SHOULD OCCUR BETWEEN MARCH - NOVEMBER FOR A MINIMUM OF 2 YEARS AND UP TO 4 YEARS. AFTER 2 YEARS THE SITE SHOULD BE EVALUATED FOR SUCCESS OF INVASIVES CONTROL AND MONITORED ANNUALLY UNTIL ALL INVASIVES HAVE BEEN SUCCESSFULLY ERADICATED. SINCE INVASIVES LIKELY OCCUR ON ADJACENT PROPERTIES, IT IS LIKELY THAT THE SITE WILL REQUIRE CONTINUOUS MONITORING TO ENSURE ADEQUATE INVASIVES


PRIOR TO BEGINNING INVASIVE CONTROL, IDENTIFY AREAS OF EACH PLANT TO BE ERADICATED. UTILIZE A LICENSED HERBICIDE APPLICATOR AND OBTAIN APPROVAL FOR USE OF HERBICIDES BY MNCPPC.

CARE SHALL BE TAKEN NOT TO DAMAGE TRUNKS OF TREES AND NATIVE VEGETATION. ONLY HAND TOOLS SHOULD BE USED TO AVOID UNNECESSARY DISTURBANCE TO NATIVE VEGETATION AND SOIL. MOTORIZED WHEELED EQUIPMENT USED FOR HAULING SHALL NOT BE DRIVEN INTO FOREST AREA; IT SHOULD BE PARKED IN THE OPEN AREAS ADJACENT TO THE AREAS WHERE INVASIVE SPECIES ARE BEING CONTROLLED. ALL INVASIVE SPECIES CONTROL WORK SHALL BE DONE BY OR UNDER THE SUPERVISION OF A CERTIFIED ARBORIST OR APPROPRIATE LICENSED/QUALIFIED PROFESSIONAL. ALL CUT VEGETATIVE MATERIAL LESS THAN 2" DIAMETER SHALL BE BAGGED AND DISPOSED OF IN THE LANDFILL; ALL MATERIAL GREATER THAN 2" DIAMETER SHALL BE CUT TO ALLOW CONTACT WITH THE GROUND, THUS ENCOURAGING DECOMPOSITION; MULCHING OF MATERIALS IS NOT PERMITTED ON-SITE AND NOT RECOMMENDED OFF-SITE.

INVASIVE PLANT REMOVAL SHALL BE COMPLETED PRIOR TO COMPLETION OF 5 YEAR MAINTENANCE AND MANAGEMENT PLANS AND CONFORM TO THE RECOMMENDATIONS OF THIS INVASIVE PLANT REMOVAL PLAN PREPARED BY DAVID L. TAYLOR, RLA DATED MAY 24, 2013.

POST CONSTRUCTION EVALUATION OF SPECIMEN TREES

POST CONSTRUCTION EVALUATION AND OPINION OF LONG-TERM SURVIVABILITY OF SPECIMEN TREES 229, 230, AND 232 SHALL BE PERFORMED BY A CERTIFIED ARBORIST AND/OR LICENSED TREE EXPERT



1. ATTACHMENT OF SIGNS TO TREES IS PROHIBITED. 2. SIGNS SHOULD BE PROPERLY MAINTAINED. 3. AVOID INJURY TO ROOTS WHEN PLACING POSTS FOR THE SIGNS. 4. SIGNS SHOULD BE POSTED TO BE VISIBLE TO ALL CONSTRUCTION PERSONNEL FROM ALL DIRECTIONS. 5. SIGNS SHOULD BE INSTALLED AT SAME TIME AS TREE PROTECTION DEVICE. 6. LOCATE SIGNS APPROXIMATELY EVERY 50' ALONG FENCING. 7. SIGNS SHOULD BE IN PLACE IMMEDIATELY FOLLOWING STAKE OUT OF L.O.D., AND

PRESERVATION OR REFORESTATION SIGN, THE TWO SIGNS MAY BE POSTED ON A


8. WHEN THE SPECIMEN TREE SIGN IS LOCATED WITHIN 10' OF EITHER A

REMAIN IN PLACE IN PERPETUITY.

SCALE: NTS

SINGLE POST.

SPECIMEN TREE SIGN



1. ATTACHMENT OF SIGNS TO TREES IS PROHIBITED. 2. SIGNS SHOULD BE PROPERLY MAINTAINED. 3 AVOID INJURY TO ROOTS WHEN PLACING POSTS FOR THE SIGNS. 4 SIGNS SHOULD BE POSTED TO BE VISIBLE TO ALL CONSTRUCTION PERSONNEL FROM ALL DIRECTIONS. 5. SIGNS SHOULD BE INSTALLED AT SAME TIME AS TREE PROTECTION DEVICE. 6. LOCATE SIGNS APPROXIMATELY EVERY 50' ALONG FENCING.

REMAIN IN PLACE IN PERPETUITY.

WOODLAND PRESERVATION AREA SIGN SCALE: NTS

7. SIGNS SHOULD BE IN PLACE IMMEDIATELY FOLLOWING STAKE OUT OF L.O.D., AND

TREE PRESERVATION AND RETENTION NOTES

1. ALL WOODLANDS DESIGNATED ON THIS PLAN FOR PRESERVATION ARE THE RESPONSIBILITY OF THE PROPERTY OWNER. THE WOODLAND AREAS SHALL REMAIN IN A NATURAL STATE. THIS INCLUDES THE CANOPY TREES AND UNDERSTORY VEGETATION. A REVISED TREE CONSERVATION PLAN IS REQUIRED PRIOR TO CLEARING WOODLAND AREAS THAT ARE NOT SPECIFICALLY IDENTIFIED TO BE CLEARED ON THE APPROVED TCP2.

2. TREE AND WOODLAND CONSERVATION METHODS SUCH AS ROOT PRUNING SHALL BE CONDUCTED AS NOTED ON THIS PLAN. 3. THE LOCATION OF ALL TEMPORARY TREE PROTECTION FENCING (TPFs) SHOWN ON THIS PLAN SHALL BE FLAGGED OR STAKED IN THE FIELD PRIOR TO THE

PRE-CONSTRUCTION MEETING. UPON APPROVAL OF THE LOCATIONS BY THE COUNTY INSPECTOR, INSTALLATION OF THE TPFs MAY BEGIN. 4. ALL TEMPORARY TREE PROTECTION FENCING REQUIRED BY THIS PLAN SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF CLEARING AND GRADING OF THE SITE AND SHALL REMAIN IN PLACE UNTIL THE BOND IS RELEASED FOR THE PROJECT. FAILURE TO INSTALL AND MAINTAIN TEMPORARY OR PERMANENT TREE PROTECTIVE DEVICES IS A VIOLATION OF THIS TCP2.

5. WOODLAND PRESERVATION AREAS SHALL BE POSTED WITH SIGNAGE AS SHOWN ON THE PLANS AT THE SAME TIME AS THE TEMPORARY TPF INSTALLATION. THESE SIGNS MUST REMAIN IN PERPETUITY.

REMOVAL OF HAZARDOUS TREES OR LIMBS BY DEVELOPERS OR BUILDERS

6. THE DEVELOPER AND/OR BUILDER IS RESPONSIBLE FOR THE COMPLETE PRESERVATION OF ALL FORESTED AREAS SHOWN ON THE APPROVED PLAN TO REMAIN UNDISTURBED. ONLY TREES OR PARTS THEREOF DESIGNATED BY THE COUNTY AS DEAD, DYING, OR HAZARDOUS MAY BE REMOVED.

7. A TREE IS CONSIDERED HAZARDOUS IF A CONDITION IS PRESENT WHICH LEADS A CERTIFIED ARBORIST OR LICENSED TREE EXPERT TO BELIEVE THAT THE TREE OR A PORTION OF THE TREE HAS A POTENTIAL TO FALL AND STRIKE A STRUCTURE, PARKING AREA, OR OTHER HIGH USE AREA AND RESULT IN PERSONAL INJURY OR PROPERTY DAMAGE. 8. DURING THE INITIAL STAGES OF CLEARING AND GRADING, IF HAZARDOUS TREES ARE PRESENT, OR TREES ARE PRESENT THAT ARE NOT HAZARDOUS BUT

ARE LEANING INTO THE DISTURBED AREA, THE PERMITEE SHALL REMOVE SAID TREES USING A CHAIN SAW. CORRECTIVE MEASURES REQUIRING THE REMOVAL OF THE HAZARDOUS TREE OR PORTIONS THEREOF SHALL REQUIRE AUTHORIZATION BY THE COUNTY INSPECTOR. ONLY AFTER APPROVAL BY THE INSPECTOR MAY THE TREE BE CUT BY CHAINSAW TO NEAR THE EXISTING GROUND LEVEL. THE STUMP SHALL NOT BE REMOVED OR COVERED WITH SOIL, MULCH OR OTHER MATERIALS THAT WOULD INHIBIT SPROUTING. 9. IF A TREE OR TREES BECOME HAZARDOUS PRIOR TO BOND RELEASE FOR THE PROJECT, DUE TO STORM EVENTS OR OTHER SITUATIONS NOT RESULTING

FROM AN ACTION BY THE PERMITEE, PRIOR TO REMOVAL, A CERTIFIED ARBORIST OR A LICENSED TREE EXPERT MUST CERTIFY THAT THE TREE OR THE PORTION OF THE TREE IN QUESTION HAS A POTENTIAL TO FALL AND STRIKE A STRUCTURE, PARKING AREA, OR OTHER HIGH USE AREAAND MAY RESULT IN PERSONAL INJURY OR PROPERTY DAMAGE. IF A TREE OR PORTIONS THEREOF ARE IN IMMINENT DANGER OF STRIKING A STRUCTURE, PARKING AREA, OR OTHER HIGH USE AREA AND MAY RESULT IN PERSONAL INJURY OR PROPERTY DAMAGE THEN THE CERTIFICATION IS NOT REQUIRED AND THE PERMITEE SHALL TAKE CORRECTIVE ACTION IMMEDIATELY. THE CONDITION OF THE AREA SHALL BE FULLY DOCUMENTED THROUGH PHOTOGRAPHS PRIOR TO CORRECTIVE ACTION BEING TAKEN. THE PHOTOS SHALL BE SUBMITTED TO THE INSPECTOR FOR DOCUMENTATION OF THE DAMAGE.

IF CORRECTIVE PRUNING MAY ALLEVIATE A HAZARDOUS CONDITION, THE CERTIFIED ARBORIST OR A LICENSED TREE EXPERT MAY PROCEED WITHOUT FURTHER AUTHORIZATION. THE PRUNING MUST BE DONE IN ACCORDANCE WITH THE LATEST EDITION OF THE APPROPRIATE ANSI A-300 PRUNING STANDARDS. THE CONDITION OF THE AREA SHALL BE FULLY DOCUMENTED THROUGH PHOTOGRAPHS PRIOR TO CORRECTIVE ACTION BEING TAKEN. THE PHOTOS SHALL BE SUBMITTED TO THE INSPECTOR FOR DOCUMENTATION OF THE DAMAGE.

DEBRIS FROM THE TREE REMOVAL OR PRUNING THAT OCCURS WITHIN 35 FEET OF THE WOODLAND EDGE MAY BE REMOVED AND PROPERLY DISPOSED OF BY RECYCLING, CHIPPING OR OTHER ACCEPTABLE METHODS. ALL DEBRIS THAT IS MORE THAN 35 FEET FROM THE WOODLAND EDGE SHALL BE CUT UP TO ALLOW CONTACT WITH THE GROUND, THUS ENCOURAGING DECOMPOSITION. THE SMALLER MATERIALS SHALL BE PLACED INTO BRUSH PILES THAT WILL SERVE AS WILDLIFE HABITAT.

TREE WORK TO BE COMPLETED WITHIN A ROAD RIGHT-OF-WAY REQUIRES A PERMIT FROM THE MARYLAND DEPARTMENT OF NATURAL RESOURCES UNLESS THE TREE REMOVAL IS SHOWN WITHIN THE APPROVED LIMITS OF DISTURBANCE ON A TCP2. THE WORK IS REQUIRED TO BE CONDUCTED BY A LICENSED

10. WORK ON THIS PROJECT WILL BE INITIATED IN SEVERAL PHASES. ALL TEMPORARY TPFs REQUIRED FOR A GIVEN PHASE SHALL BE INSTALLED PRIOR TO ANY DISTURBANCE WITHIN THAT PHASE OF WORK.

11. DEBRIS PILES SHOWN IN WOODLAND PRESERVATION AREAS SHALL BE REMOVED BY HAND WITHOUT THE USE OF MECHANICAL EQUIPMENT WITHIN THE PRESERVATION AREA. CHAINS MAY BE USED TO PULL DEBRIS OUTOF THE PRESERVATION AREAS. CAUTION MUST BE USED NOT TO DAMAGE REMAINING VEGETATION.

AFFORESTATION AND REFORESTATION NOTES

NOXIOUS, INVASIVE, AND NON-NATIVE VEGETATION WITHIN THE REFORESTATION AREAS IS ACCEPTABLE.

1. ALL AFFORESTATION AND REFORESTATION BONDS, BASED ON SQUARE FOOTAGE, SHALL BE POSTED WITH THE COUNTY PRIOR TO THE ISSUANCE OF ANY PERMITS. THESE BONDS WILL BE RETAINED AS SURETY UNTIL ALL REQUIRED ACTIVITIES HAVE BEEN SATISFIED OR THE REQUIRED TIMEFRAME FOR MAINTENANCE HAS PASSED WHICHEVER IS LONGER.

2. THE PLANTING OF AFFORESTATION OR REFORESTATION AREAS SHALL BE COMPLETED IN SEQUENCE WITH DEVELOPMENT. SEEDLING PLANTING IS TO OCCUR FROM NOVEMBER THROUGH MAY ONLY AS LONG AS THE GROUND IS NOT FROZEN. PLANTING WITH LARGER CALIPER STOCK OR CONTAINERIZED STOCK MAY BE DONE AT ANY TIME PROVIDED A DETAILED MAINTENANCE SCHEDULE IS PROVIDED.

3. IF PLANTING CANNOT OCCUR DUE TO PLANTING CONDITIONS, THE DEVELOPER OR PROPERTY OWNER SHALL INSTALL THE FENCING AND SIGNAGE IN ACCORDANCE WITH THE APPROVED TYPE 2 TREE CONSERVATION PLAN. PLANTING SHALL THEN BE ACCOMPLISHED DURING THE NEXT PLANTING SEASON. IF PLANTING IS DELAYED BEYOND THE TRANSFER OF THE PROPERTY TITLE TO THE HOMEOWNER, THE DEVELOPER OR BUILDER SHALL OBTAIN A SIGNED STATEMENT FROM THE PURCHASER INDICATING THAT THEY UNDERSTAND THAT THE REFORESTATION AREA IS LOCATED ON THEIR PROPERTY AND THAT REFORESTATION WILL OCCUR DURING THE NEXT PLANTING SEASON. A COPY OF THAT DOCUMENT SHALL BE PRESENTED TO THE GRADING INSPECTOR AND 4. REFORESTATION AREAS SHALL NOT BE MOWED. THE MANAGEMENT OF COMPETING VEGETATION AROUND INDIVIDUAL TREES AND THE REMOVAL OF

PLACE UNTIL THE PERMANENT TREE PROTECTION FENCING IS INSTALLED WITH THE REQUIRED PLANTING. THE TEMPORARY FENCING IS NOT REQUIRED TO BE INSTALLED IF THE PERMANENT FENCING IS INSTALLED PRIOR TO CLEARING AND GRADING OF THE SITE. FAILURE TO INSTALL AND MAINTAIN TEMPORARY

OR PERMANENT TREE PROTECTIVE FENCING IS A VIOLATION OF THIS TCP2. 6. AFFORESTATION/REFORESTATION AREAS SHALL BE POSTED WITH NOTIFICATION SIGNAGE, AS SHOWN ON THE PLANS, AT THE SAME TIME AS THE PERMANENT PROTECTION FENCING INSTALLATION. THESE SIGNS SHALL REMAIN IN PERPETUITY. 7. THE COUNTY INSPECTOR SHALL BE NOTIFIED PRIOR TO SOIL PREPARATION OR INITIATION OF ANY TREE PLANTING ON THIS SITE

8. AT TIME OF ISSUANCE OF THE FIRST PERMIT, THE FOLLOWING INFORMATION SHALL BE SUBMITTED TO THE M-NCPPC PLANNING DEPARTMENT REGARDING

THE CONTRACTOR RESPONSIBLE FOR IMPLEMENTATION OF THIS PLAN: CONTRACTOR NAME; BUSINESS NAME (IF DIFFERENT); ADDRESS; AND PHONE

NUMBER. RESULTS OF ANNUAL SURVIVAL CHECKS FOR EACH OF THE REQUIRED FOUR YEARS AFTER TREE PLANTING SHALL BE REPORTED TO THE

5. ALL REQUIRED TEMPORARY TREE PROTECTION FENCING SHALL BE INSTALLED PRIOR TO THE CLEARING AND GRADING OF THE SITE AND SHALL REMAIN IN

M-NCPPC, PLANNING DEPARTMENT. 9. FAILURE TO ESTABLISH THE AFFORESTATION OR REFORESTATION WITHIN THE PRESCRIBED TIME FRAME WILL RESULT IN THE FORFEITURE OF THE REFORESTATION BOND AND/OR A VIOLATION OF THIS PLAN INCLUDING THE ASSOCIATED \$9.00 PER SQUARE FOOT PENALTY UNLESS THE COUNTY

PROTECTION OF REFORESTATION AND AFFORESTATION AREAS BY INDIVIDUAL HOMEOWNERS

REFORESTATION FENCING AND SIGNAGE SHALL REMAIN IN PLACE IN ACCORDANCE WITH THE APPROVED TYPE 2 TREE CONSERVATION PLAN. REFORESTATION AREAS SHALL NOT BE MOWED; HOWEVER, THE MANAGEMENT OF COMPETING VEGETATION AND REMOVAL OF NOXIOUS, INVASIVE, AND NON-NATIVE VEGETATION AROUND INDIVIDUAL TREES IS ACCEPTABLE.


REFORESTATION AND AFFORESTATION CERTIFICATION

ALL REFORESTATION AND ASSOCIATED FENCING AND SIGNS SHALL BE INSTALLED PRIOR TO THE ISSUANCE OF A BUILDING PERMIT FOR LOTS ABUTTING REFORESTATION AREAS. A CERTIFICATION SHALL BE PREPARED BY A QUALIFIED PROFESSIONAL TO PROVIDE VERIFICATION THAT THE REFORESTATION HAS BEEN COMPLETED. THE CERTIFICATION SHALL INCLUDE, AT A MINIMUM, PHOTOS OF THE REFORESTATION AREA AND ASSOCIATED FENCING IN RELATION TO THE ABUTTING LOT, WITH LABELS ON THE PHOTOS IDENTIFYING THE LOCATIONS, AND A PLAN SHOWING THE LOCATIONS WHERE THE PHOTOGRAPHS WERE TAKEN.

OFF-SITE WOODLAND CONSERVATION NOTE:

INSPECTOR APPROVES A WRITTEN EXTENSION.

PRIOR TO THE ISSUANCE OF THE FIRST GRADING PERMIT FOR THE DEVELOPMENT SHOWN ON THIS TCP2, ALL OFF SITE WOODLAND CONSERVATION REQUIRED BY THIS PLAN SHALL BE IDENTIFIED ON AN APPROVED TCP2 PLAN AND RECORDED AS AN OFF-SITE EASEMENT IN THE LAND RECORDS OF PRINCE GEORGE'S COUNTY. PROOF OF RECORDATION OF THE OFF-SITE CONSERVATION SHALL BE PROVIDED TO THE M-NCPPC, PLANNING DEPARTMENT PRIOR TO ISSUANCE OF ANY PERMIT FOR THE ASSOCIATED PLAN.



1. ATTACHMENT OF SIGNS TO TREES IS PROHIBITED. 2. SIGNS SHOULD BE PROPERLY MAINTAINED. 3. AVOID INJURY TO ROOTS WHEN PLACING POSTS FOR THE SIGNS. 4. SIGNS SHOULD BE POSTED TO BE VISIBLE TO ALL CONSTRUCTION PERSONNEL

SCALE: NTS

FROM ALL DIRECTIONS. 5. SIGNS SHOULD BE INSTALLED AT SAME TIME AS TREE PROTECTION DEVICE. 6. LOCATE SIGNS APPROXIMATELY EVERY 50' ALONG FENCING. 7. SIGNS SHOULD BE IN PLACE IMMEDIATELY FOLLOWING STAKE OUT OF L.O.D., AND REMAIN IN PLACE IN PERPETUITY.

REFORESTATION AREA SIGN

02 2/26/08 04 6/25/09 11/18/10 03 4/25/13 R.G. PRINCE GEORGE'S COUNTY PLANNING DEPARTMENT, MNCPPC ENVIRONMENTAL PLANNING SECTION TREE CONSERVATION PLAN APPROVAL TCP-II/82/05 Approved by Date DRD# REASON FOR REVISION 8/15/06 DSP-06047, 02,04, & 05 LORI SHIRLEY MEGAN K. REISER 1/24/14 DSP-06047-03 Mary Reiner 10/14 STAFFLEVEL manuxpeise 7/1/16 Staff level specimen tree remova

FOR LOCATION OF UTILITIES CALL

8-1-1 OR 1-800-257-7777

OR LOG ON TO

www.call811.com

http://www.missutility.net

48 HOURS IN ADVANCE OF ANY WORK

IN THIS VICINITY

FORMATION CONCERNING UNDERGROUN

UTILITIES WAS OBTAINED FROM AVAILABLE

RECORDS BUT THE CONTRACTOR MUST

DETERMINE THE EXACT LOCATION AND

ELEVATION OF THE MAINS BY DIGGING TEST PITS

BY HAND AT ALL UTILITY CROSSINGS WELL IN

ADVANCE OF THE START OF EXCAVATION

8/17/08

M.N.C.P.P.C. APPROVALS

For Condition of Approval see Site Plan Cover Sheet or Approval The Revisions Listed Below Apply to this Sheet

PROJECT NAME: BALK HILL VILLAGE

Approval or Approval Reviewer's Signature

7/18/06 R.G.

PROJECT NUMBER: DSP-04067

Dewberry

10003 DEREKWOOD LANE Consultants LLC LANHAM, MD 20706 Formerly known as 301.731.0188 (FAX) Dawberry & Davis LLC www.dewberry.com

Dewberry Dewberry

OWNER/APPLICANT D.R. HORTON, INC 1356 BEVERLY ROAD, STE. 300

MCLEAN, VIRGINIA 22101 TEL (703) 385-8001 CONTACT

INES E. VEGA TEL: 703.385.8001 IEVEGA@DRHORTON.COM



I HEREBY CERTIFY THAT THESE DULY REGISTERED LANDSCAPE ARCHITECT UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 3108, EXPIRATION DATE: OCTOBER 3, 2015.


SCALE


AS SHOWN


12/02/14 NB Address staff comments. Account for Ruby Lockhart 11/14/13 NB Address staff comments. DATE BY Description REVISIONS APPROVED BY LRB CHECKED BY MAY 24, 2013 DATE TITLE


TYPE II TREE CONSERVATION PLAN **DETAIL SHEET**


PROJECT NO. 50059112













ROOT PRUNING 3








1. SOURCE: ADAPTED FROM FOREST CONSERVATION MANUAL, 1991. 2. MULCHING NEWLY PLANTED SEEDLINGS HELPS THE SOIL RETAIN MOISTURE

AND PROTECTS THE SEEDLING FROM COMPACTION AND STEM INJURIES.

SEEDLING PLANTING TECHNIQUES (MANUAL) SCALE: NTS




1. SOURCE: ADAPTED FROM STEVE CLARK & ASSOCIATES / ACRT, INC.

2. SILT FENCE TO BE HEELED INTO THE SOIL. 3. WIRE, SNOW FENCE, ETC FOR TREE PROTECTION ONLY.

4. BOUNDARIES OF RETENTION AREA WILL BE ESTABLISHED AS A PART OF THE FOREST CONSERVATION PLAN REVIEW PROCESS. 5. BOUNDARIES OF RETENTION AREA SHALL BE STAKED AND FLAGGED PRIOR

TO INSTALLING THE DEVICE. 6. AVOID ROOT DAMAGE WHEN PLACING ANCHOR POSTS. DEVICE SHALL BE PROPERLY MAINTAINED THROUGHOUT CONSTRUCTION. 8. TREE PROTECTION SIGNS ARE REQUIRED. SEE DETAILS, THIS SHEET. 9. LOCATE FENCE OUTSIDE OF THE CRITICAL ROOT ZONE.

SILT FENCE AND TREE PROTECTION SCALE: NTS





NOTES: 1. SOURCE: UNKNOWN

2. MULCHING NEWLY PLANTED SEEDLINGS HELPS THE SOIL RETAIN MOISTURE AND PROTECTS THE SEEDLING FROM COMPACTION AND STEM INJURIES.

SEEDLING PLANTING TECHNIQUES (MACHINE) SCALE: NTS

		HASE 2 SECTION "O" Acreage				0.30	
Species		Planting Stock					
Botanical Name	Common Name	Size	Credits/Unit	Туре	Quantity	Cred	
	Shade Tree	2.5" - 3" Caliper	5	B&B	14		
SEE NOTE #3	Omamental	1.5" - 1.75" Caliper	3	B&B	14		
	Evergreen	6'-8' HT (1.5" Caliper)	5	B&B	14		
Acer rubrum	Red Maple	Seedling: 6"-18" HT.	1	Bare Root	6		
Liriodendron tulipifera	Yellow Poplar	Seedling: 6"-18" HT.	1	Bare Root	6		
Liquidambar styraciflua	Sweetgum	Seedling: 6"-18" HT.	1	Bare Root	6		
		The state of the s	De servicement	Reforestation	Units Provided		
ikan mahaman ya mahin di kalimasar da man kalima ka sa kaman binaha mbanda anda anda sa da sa kaba sa sa sa sa	i de desembración de dese en contrata de la braga en conservor en entre de la referencia la la la la la la la l La la	in global to months a factor on the first first first first and the many many on the many of the second of the	Tota	l Reforestation	Units Required		
والمراقة والمراقية والمتوادية والمداومة والمدارية والمتاوية والمدارية والمدارية والمراقبة والمتاوية والمدارة والمدارة			Agrico angela an ingrina na magana na mag Bangana na magana na Bangana na magana na ma	kun epi fing philippila yan min menjan elamini km	Excess		
	FORES TATION AREA Pecies	HASE 2 SECTION P	Planting Sto	ock	Acreage	0.0 Refores	
1 7							
Botanical Name	Common Name	Size	Credits/Unit	Type	Quantity	Cred	
	Common Name Shade Tree	2.5" - 3" Caliper	Credits/Unit 5	Type B&B	Quantity 4	Ure:	
		2.5" - 3" Caliper 1.5" - 1.75" Caliper	CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR	B&B B&B	Quantity 4	Cred	
Botanical Name	Shade Tree	2.5" - 3" Caliper 1.5" - 1.75" Caliper 6'-8' HT (1.5" Caliper)	5	B&B	Quantity 4 0 3		
Botanical Name	Shade Tree Omamental	2.5" - 3" Caliper 1.5" - 1.75" Caliper	5 3	B&B B&B	4 0	<u> </u>	
Botanical Name SEE NOTE #3	Shade Tree Omamental Evergreen	2.5" - 3" Caliper 1.5" - 1.75" Caliper 6'-8' HT (1.5" Caliper)	5 3	B&B B&B B&B Bare Root Bare Root	4 0 3 10		
Botanical Name SEE NOTE #3 Quercus Phellos	Shade Tree Omamental Evergreen Willow oak	2.5" - 3" Caliper 1.5" - 1.75" Caliper 6'-8' HT (1.5" Caliper) Seedling: 6"-18" HT.	5 3 5	B&B B&B B&B Bare Root Bare Root	4 0 3 10		
Botanical Name SEE NOTE #3 Quercus Phellos	Shade Tree Omamental Evergreen Willow oak	2.5" - 3" Caliper 1.5" - 1.75" Caliper 6'-8' HT (1.5" Caliper) Seedling: 6"-18" HT.	5 3 5 1	B&B B&B B&B Bare Root Bare Root Reforestation	4 0 3 10		
Botanical Name SEE NOTE #3 Quercus Phellos	Shade Tree Omamental Evergreen Willow oak	2.5" - 3" Caliper 1.5" - 1.75" Caliper 6'-8' HT (1.5" Caliper) Seedling: 6"-18" HT.	5 3 5 1	B&B B&B B&B Bare Root Bare Root Reforestation	4 0 3 10 10 Units Provided		





1. SOURCE: UNKNOWN

TULIP POPLAR

BLACK CHERRY

NOTE: THE NUMBER OF 1° CALIPER TREES PROVIDED AS AGREED TO WITH KATINA SHOULARS 6/13/2016.

Prunus serotina

Quercus alba

WHITE OAK

FOREST PROTECTION DEVICE ONLY. RETENTION AREA WILL BE SET AS PART OF THE REVIEW PROCESS. 4. BOUNDARIES OF RETENTION AREAS SHALL BE STAKED AND FLAGGED PRIOR TO INSTALLING THE

5. ROOT DAMAGE SHALL BE AVOIDED WHEN INSTALLING THE DEVICE. 6. PROTECTIVE SIGNAGE IS REQUIRED; 50' MAX SPACING ALONG ALL LODS AND / OR STREAM

7. DEVICE SHALL BE INSTALLED PRIOR TO THE ISSUANCE OF BUILDING PERMITS UNLESS ADDITIONAL GRADING IN THE REFORESTATION AREA WILL BE REQUIRED IN CONJUNCTION WITH

BE INSTALLED IMMEDIATELY UPON COMPLETION AND STABILIZATION OF THE GRADING.

PERMANENT (SPLIT RAIL) TREE PROTECTION FENCE SCALE: NTS

THE BUILDING PERMIT, IN WHICH CASE THE REFORESTATION/ AFFORESTATION FENCING SHALL


REPLACEMENT PLANTINGS FOR SPECIMEN TREE #229 PLANTING SCHEDULE ROOT NOTES NATIVE QTY KEY BOTANICAL/COMMON NAME SIZE SHADE TREES Liriodendron tulipifera 1.0" CAL. B & B SINGLE LEADER


1.0" CAL.

1.0" CAL.

B & B SINGLE LEADER

B&B SINGLE LEADER





M.N	.C.P.F	P.C. APPRO	VALS
PROJECT	NAME: BAL	K HILL VILLAGE	
PROJECT	NUMBER: [DSP-04067	agrangs aga gilinay sa arreng a kagaligaga pilipugan ya ribagsah sa re
For Conditi Th	on of Approva e Revisions Li	l see Site Plan Cover Sheet sted Below Apply to this She	or Approval et
For Conditi The	on of Approva e Revisions Li Approval Date	al see Site Plan Cover Sheet sted Below Apply to this She Reviewer's Signature	or Approval et Certification Date
	Approval		Certification
	Approval Date	Reviewer's Signature	Certification Date
Approval or Revision #	Approval Date 7/18/06	Reviewer's Signature R.G.	Certification Date 8/17/06
Approval or Revision #	Approval Date 7/18/06 2/26/08	Reviewer's Signature R.G. J.R.	Certification Date 8/17/06 2/28/08

specimen tree removal

	PRINCE GEORGE	's coun	NTY PLANNING DE	PARTMENT,	MNCF	PPC
	· ·		NTAL PLANNING			
	IRE		ERVATION PLAN A	IPPROVAL		
			CP-II/82/05			
	Approved by	Date	DRD#	REASON	FOR	REVISION
equarings h	LORI SHIRLEY	8/15/06	DSP-06047, 02,04, & 05		ndengti sek sesting galanna miliansiya til tilb	Den de delete forde de desegyal val realizações de delete de la delete de delete de de delete de de delete de d
	MEGAN K. REISER	1/24/14	DSP-06047-03		Name of the last o	n Street on which the committee of the c
	T	1	}	ALCADIMO CAL	STREET STREET	COMME

MEGANIK. REISER 12/10/14 STAFF LEVEL

Magnik Reiser 7/1/16 Staff level

10003 DEREKWOOD LANE Consultants LLC LANHAM, MD 20706 Formerly known as 301.731.0188 (FAX) Dewberry & Davis LLC www.dewberry.com

Dewberry

OWNER/APPLICANT D.R. HORTON, INC 1356 BEVERLY ROAD, STE. 300 MCLEAN, VIRGINIA 22101 TEL (703) 385-8001

Dewberry

CONTACT INES E. VEGA TEL: 703.385.8001 IEVEGA@DRHORTON.COM

L HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY REGISTERED LANDSCAPE ARCHITECT UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 3108, EXPIRATION DATE: OCTOBER 3, 2017. KEY PLAN

SCALE

AS SHOWN

4	03/10/16	SGT	Specimen Tree planting replacement / Permanent fencing around preservation area "D"
3	12/02/14	NB	Address staff comments.
2	11/25/14	NB	Account for Ruby Lockhart Construction.
1	11/14/13	NB	Address staff comments.
No.	DATE	BY	Description

APPROVED BY LRB CHECKED BY MAY 24, 2013 TITLE


CAP, EDL


TYPE II TREE CONSERVATION **PLAN**


DETAIL SHEET


PROJECT NO. 50059112


SHEET NO.
































14 OF 17

SHEET NO.







Dewberry

Dewberry
Consultants LLC
Formerly known as 301.731.5551
301.731.0188 (FAX) Dewberry & Davis LLC

OWNER/APPLICANT D.R. HORTON, INC 1356 BEVERLY ROAD, STE. 300 MCLEAN, VIRGINIA 22101 TEL (703) 385-8001

> CONTACT INES E. VEGA TEL: 703.385.8001 IEVEGA@DRHORTON.COM

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY REGISTERED LANDSCAPE ARCHITECT UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 3108, EXPIRATION DATE: OCTOBER 3, 2015.

1"=30"

3	12/02/14	NB	Address staff comments.
2	11/25/14	NB	Account for Ruby Lockhart Construction.
1	11/14/13	NB	Address staff comments.
No.	DATE	BY	Description

LND MAY 24, 2013

TYPE II TREE CONSERVATION PLAN

50059112 PROJECT NO.