When afforestation/reforestation is proposed:

Afforestation and Reforestation Notes

a. All afforestation and reforestation points, based on acceptable topology, shall be posted with the county prior to the issuance of any permits. These points will be retained as survey until all required activities have been completed or the required timeframe for maintenance has passed whichever is longer.

b. The planting of afforestation or reforestation areas shall be completed prior to the issuance of the first building permit. (The planting note may be modified as necessary to address when during permits are applied to the proposed planting area.) Seed by planting a to occur from November through May only. No planting shall be done while ground is frozen. Planting with larger caliper stock or containerized stock may be done at any time provided a detailed maintenance schedule is provided.

c. If planting cannot occur due to planting conditions, the developer or property owner shall install the fencing and signage in accordance with the approved Type 2 Tree Conservation Plan. Planting shall then be accomplished during the next planting season. If planting is delayed beyond the transfer of the property title to the homeowner, the developer or builder shall obtain a signed statement from the purchaser indicating that they understand that the reforestation area is located on their property and that reforestation will occur during the next planting season. A copy of that document shall be presented to the Grading Inspector and the County.

d. Reforestation areas shall not be mowed. The management of competing vegetation around individual trees and the removal of noxious, invasive and non-native vegetation within the reforestation areas is acceptable.

e. A required temporary tree protection fencing shall be installed prior to the clearing and grading of the site and then retain in place until the permanent tree protection fencing is installed with the required plantings. The temporary fencing is not required to be installed if the permanent fencing is installed prior to clearing and grading of the site. Failure to install and maintain temporary or permanent tree protective fencing is a violation of this TCP2.

f. Afforestation/reforestation areas shall be posted with notification signage, as shown on the plans, at the same time as the permanent protection fencing installation. These signs shall remain in perpetuity.

g. The county inspector shall be notified prior to soil preparation or initiation of any tree planting on this site.

h. At time of issuance of the first permit, the following information shall be submitted to the M-NCPPC Planning Department regarding the contractor responsible for implementation of the plan: contractor name; business name (if different); address; and phone number.

August 2010 — A-3, TCP2-1 Page 4

Results of annual survival checks for each of the required four years after tree planting shall be reported to the M-NCPPC, Planning Department.

Failure to establish the afforestation/reforestation within the prescribed time frame will result in the forfeiture of the reforestation bond and/or a violation of this plan including the associated $5.00 per square foot penalty unless the county inspector approves a written extension.

Planting Specification Notes

1. Quantity: (See Plant Schedule)
2. Type: (See Plant Schedule)
3. Plant Quality Standards: The plants selected shall be healthy and sturdy representatives of their species. Seedlings shall have a minimum top growth of 18". The diameter at the root collar (the part of the root just below ground level) shall be at least 3/8". The roots shall be well developed and at least 8" long. No more than twenty -five percent (25%) of the root system (both primary and auxiliary fibrous roots shall be present.

   Plants that do not have an abundance of well developed terminal buds on the leaders and branches shall be rejected.

   Plants shall be shipped by the nursery immediately after lifting from the field or removal from the green house and planted immediately upon receipt by the landscape contractor.

   If the plants cannot be planted immediately after delivery to the reforestation site, they shall be stored in the shade with their root masses protected from direct exposure to sun and wind by the use of straw, peat moss, compost, or other suitable material and shall be maintained through periodic watering, until the time of planting.
4. Plant Handling: the quantity of seedlings taken to the field shall not exceed the quantity that can be planted in a day. Seedlings, once removed from the nursery or temporary storage area shall be planted immediately.
5. Timing of Planting: The best time to plant seedlings is while they are dormant, prior to spring budding. The most suitable months for planting are March and April, when the soil is moist and the ground has thawed from March through November. No planting shall be done while ground is frozen. Planting shall occur within one growing season of the issuance of grading. Starting permits and/or reaching the final grades and stabilization of planting areas.
6. Seedling Planting: Tree seedlings shall be hand planted using a dibble bar or sharp-shooter shovel. It is important that the seedling be placed in the hole so that the roots can spread out naturally. they should not be twisted, balled up or bent. Moist soil should then be packed firmly around the roots to eliminate air pockets. The seedling should be planted so that collar is just below the ground surface. Air pockets should not be left after closing the hole which would allow the roots to dry out. See planting details for further explanation. If the

August 2010 — A-3, TCP2-2 Page 5

...stockpiler wishes to plant by another method, the preparer of the tree conservation plan must be contacted and give the approval before planting may begin.

7. Stocking: See Plant Schedule and/or #1 Planting Plan for stocking requirements. Also refer to the Planting Layout detail for a description of the general planting theory.

8. Bird: Note the time, location and a grading operations, as to test and be constructed as necessary to meet the germination and soil amendments. If any, and necessary to create good tree growing conditions. Soil samples shall be taken at a rate that provides one soil sample for each area that appears to have a different soil type. If the entire area appears uniform, then only one sample is necessary, and submitted for testing to a private company. The company of choice shall make recommendations for maintaining the existing soil. The soil will be tested for phosphorous, potassium, ph, buffer pH, magnesium, phosphorous, potassium, calcium and organic matter.

9. Soil Improvement Measures: the soil shall then be improved according to the recommendations made by the testing company.

10. Planting and Signage: Final procedure before planting shall be placed on the maple and/or deciduous trees. Planting of trees and the final procedures hence shall be initiated upon completion of planting operations unless it was initiated during item initial stages of development. Signs shall be posted per the signage detail on this sheet.

11. Planting method: Consult the Planting Details shown on this plan

12. Mulching: Apply two inch thick layer of wood chip or shredded hardwood mulch rac noted to each planting site rate detail shown on the plans.

13. Groundcover Establishment: the remaining disturbed area between seedling planting sites shall be seeded and stabilized with white clover seed at the rate of 5 lbs acre.

14. Mowing: No mowing shall be allowed in any planting area.

15. Survival Check for Bond Release: The seedling planting is to be checked at the end of each year for four years to assure that no less than 75% of the original planted quantity survives. If the minimum number was not been provided the area must be supplemented with additional seedlings to reach the required number at time of planting

16. Source of Seedlings, state name, address, and phone number of nursery or supplier.

Four-Year Management Plan for the Afforestation Areas

Field checks the re-afforestation area according to the following schedule:

Year 1: Site preparation and Tree Planting
Survival check once annually (September-November) see Note 1)
Watering is needed 2-4 months
Control of undesirable vegetation as needed (1 x in June and 1 x in September min.)

Year 2-3: Reinforcement planting is needed (See Note 2)
Survival checks once annually (September-November)
Control of undesirable vegetation if needed (1 x in May and 1 x in August min.)

Year 4: Reinforcement planting if needed (See Note 2)
Survival check (September -November)

1. Survival Check: Check planted stock against plant list (or as- built) by walking the site and taking inventory. Plants must show vitality. Submit field data forms (found on Check Sheets) to owner after each inspection. Remove all dead plants.
2. Reinforcement Planting: Replace dead or missing plants in sufficient quantity to bring the total number of live plants to at least 75% of the number originally planted. If a particular species suffers unusually high mortality, replace with an alternative plant type.

August 2010 — A-3, TCP2-2 Page 7

TYPE II TREE CONSERVATION PLAN NOTES

1. Cutting or clearing of woodland not in conformance with this plan or without the expressed written consent of the Planning Director or designee shall be subject to a $27.00 per square foot mitigation fee.
2. A pre-construction meeting is required prior to the issuance of grading permits. The Department of Public Works and Transportation or the Department of Environmental Resources, as appropriate shall be contacted prior to the start of any site work in order to conduct a pre-construction meeting where implementation of woodland conservation measures shown on this plan will be discussed in detail.
3. The developer or builder of the lots or parcels shown on this plan shall notify future buyers of any woodland conservation areas through the provision of a copy of this plan at time of contract signing. Future property owners are also subject to this requirement.
4. The owners of the property subject to this tree conservation plan are solely responsible for conformance to the requirements contained herein.
5. The property is within the developing tier and is zoned I-2.
6. The site is not adjacent to a roadway designated as scenic, historic, a parkway or a scenic byway.
7. The property is not adjacent to a roadway classified as Arterial or greater.
8. The site is not grandfathered under CB-27-2010, Section 25-119(d).
9. All woodlands designated on this plan for preservation are the responsibility of the property owner. The woodland areas shall remain in a natural state. This includes the canopy trees and understory vegetation. A revised tree conservation plan is required prior to clearing woodland areas that are not specifically identified to be cleared on the approved TCP II.
10. Tree and woodland conservation methods such as root pruning shall be conducted as noted on this plan.
11. The location of all temporary tree protection fencing (TPF's) shown on this plan shall be flagged or staked in the field prior to the pre-construction meeting. Upon approval of the locations by the County Inspector, installation of the TPF's may begin.
12. All temporary tree protection fencing required by this plan shall be installed prior to commencement of clearing and grading of the site and shall remain until the bond is released for the project. Failure to install and maintain temporary or permanent tree protective devices is a violation of this TCP2.
13. Woodland preservation areas shall be posted with signage as shown on the plans at the same time as the temporary TPF installation. These signs must remain in perpetuity.

REMOVAL OF HAZARDOUS TREES OR LIMBS BY DEVELOPERS OR BUILDERS

14. The developer and/or builder is responsible for the complete preservation of all forested areas shown on the approved plan to remain undisturbed. Only trees or part thereof designated by the County as dead, dying or hazardous may be removed.
15. A tree is considered hazardous if a condition is present which leads a certified arborist or licensed tree expert to believe that the tree has a potential to fall and strike a structure, parking area, or other high use area and result in personal injury or property damage.
16. During the initial stages of clearing and grading, if hazardous trees are present, or trees are present that are not hazardous but are leaning into the disturbed area, the permittee shall contact the County and chain saw. Corrective measures requiring the removal of the hazardous tree or portions thereof shall require authorization by the County inspector. Only after approval by the inspector may the tree be cut by chain saw to near the existing ground level. The stump shall not be removed or covered with soil, mulch or other materials that would inhibit sprouting.
17. If a tree or trees become hazardous prior to bond release for the project, due to storm events or other situations not resulting from an action by the permitee, prior to removal, a certified arborist or licensed tree expert must certify that the tree or the portion of the tree in question has a potential to fall and strike a structure, parking area, or other high use area and may result in personal injury or property damage. If a tree or portions thereof are in imminent danger of striking a structure, parking area, or other high use area and may result in personal injury or property damage then the certified arborist or licensed tree expert may corrective action immediately. The condition of the area shall be fully documented through photographs prior to corrective action being taken. The photos shall be submitted to the inspector for documentation of the damage.
   If corrective pruning may alleviate a hazardous condition, the certified arborist or a licensed tree expert may proceed without further authorization. The pruning must be done in accordance with the latest edition of the appropriate ANSI A-300 Pruning Standards. The condition of the area shall be fully documented through photographs prior to corrective action being taken. The photos shall be submitted to the inspector for documentation of the damage.
   Debris from the tree removal or pruning that occurs within 35 feet of the woodland edge may be removed and properly disposed of by recycling, chipping or other acceptable methods. All debris that is more than 35 feet from the woodland edge shall be cut up to allow contact with the ground, thus encouraging decomposition. The smaller materials shall be placed into brush piles that will serve as wildlife habitat.
   Tree work to be completed within a road right-of-way requires a permit from the Maryland Department of Natural Resources unless the tree removal is shown within the approved limits of disturbance on a TCP2. The work is required to be conducted by a Licensed Tree Expert.

Woodland Areas NOT Counted as Part of the Woodland Conservation Requirements

1. A revised Tree Conservation Plan is required prior to clearing any woodland area which is not specifically identified to be cleared on the most recently approved Type II TCP on file in the office of the M-NCPPC, Environmental Planning Section located on the 4th floor of the County Administration Building at 14741 Governor Oden Bowie Drive, Upper Marlboro, Maryland 20772, phone 301-952-3650 Additional mitigation will be required for the clearing of all woodlands beyond that reflected on the approved plans. Although clearing may be allowed, it may be subject to additional replacement requirements, mitigation, and fees which must be reflected on TCP revisions approved by the M-NCPPC Environmental Planning Section.
2. Homeowners or property owners may remove trees less than two (2) inches diameter, shrubs, and vines in woodland areas but not part of the Woodland Conservation requirements after all permits have been released for the subject property. This area may not be tilled or have other ground disturbances which would result in damage to tree roots. Raking the leaves and overseeding with native grasses, native flowers or native ground covers is acceptable. Seeding with invasive grasses including any variety of Kentucky 31 fescue is not acceptable.

Removal of Hazardous Trees or Hazardous Limbs By Developers or Builders

The developer and/or builder is responsible for the complete preservation of all forested areas shown on the approved plan to remain undisturbed. Only trees or parts thereof designated by the County or Maryland Environmental Resources as dead, dying, or hazardous may be removed.

1. A tree is considered hazardous if a condition is present which leads a Licensed Arborist or a Licensed Tree Expert to believe that the tree or a portion of the tree has a potential to fall and strike a structure, parking area, or other high use area and result in personal injury or property damage.
2. If a hazardous condition may be alleviated by corrective pruning, the certified arborist or a Licensed Tree Expert may proceed without further authorization. The pruning must be done in accordance with the latest edition of the ANSI A-300 Pruning Standards (Tree, Shrub, and Other Woody Plant Maintenance – Standard Practices).
3. Corrective measures requiring the removal of the hazardous tree or portions thereof shall require authorization by the building or grading inspector if there is a valid grading or building permit for the subject lots or parcels on which the trees are located. Only after approval of the appropriate inspector may the tree be cut by chainsaw to near the existing ground level. The stump may not be removed or covered with soil, mulch or other materials that would inhibit sprouting.
4. Debris from the tree removal or pruning that occurs within 35 feet of the woodland edge may be removed and properly disposed of by recycling, chipping or other acceptable methods. All debris that is more than 35 feet from the woodland edge shall be cut up to allow contact with the ground, thus encouraging decomposition. The smaller materials shall be placed into brush piles that will serve as wildlife habitat.

TYPE 2 TCP CERTIFICATION

I HEREBY CERTIFY THAT THE PLAN SHOWN HEREON CONFORMS TO THE REQUIREMENTS OF THE PRINCE GEORGE'S COUNTY WOODLAND CONSERVATION / TREE PRESERVATION ORDINANCE FOR A FOREST CONSERVATION PLAN.

7-21-16 — DATE

DOUGLAS S. HODGES — QUALIFIED PROFESSIONAL – COMAR 08.19.06.01

Property Owner Awareness Certificate

I, Jeffrey J. Felker, agent for Ponds Power Fund, hereby acknowledge that I am aware of this Type 2 Tree Conservation Plan (TCP 2) and that I understand the requirements as set forth in this TCP 2.

Jeffrey J. Felker — 7-22-16 — Date

Standard Woodland Conservation Worksheet for Prince George's County

SECTION 1:Establishing Site Information- (Enter acres for each zone)				
1 Zone	I-2			
2 Gross Tract	88.94			
3 Floodplain	0.00			
4 Previously Dedicated Land	0.00			
5 Net Tract (NTA)	88.94	0.00	0.00	
6 TCP Number			Revision #	0
7 Property Description or Subdivision Name				
8 Is this site subject to the 1989 Ordinance?(Y/N)	N			
9 Is this one (1) single family lot? (Y/N)	N			
10 Are there prior TCP approvals which include a	Y			
11 combination of this lot(s)? (Y,N)				
12 Is any portion of the property in a WC Bank?	N			
13 Break-even Point (preservation) =	13.97	acres		
14 Clearing permitted w/o reforestation	2.54	acres		

SECTION II:Determining Requirements (Enter acres for each corresponding column)	Column A WCTA/FT %	Column B Net Tract	Column C Floodplain (1:1)	Column D Off-Site Impacts (1:1)
15 Existing Woodland		16.51	0.00	
16 Woodland Conservation Threshold (WCT) =	15.00%	13.34		
17 Smaller of 15 or 16		13.34		
18 Woodland above WCT		3.17		
19 Woodland cleared		6.23	0.00	0.00
20 Woodland cleared above WCT (smaller of 16 or 17)		3.17		
21 Clearing above WCT (2.25 :1) replacement requirement		7.13		
22 Woodland cleared below WCT		3.06		
23 Clearing below WCT (2:1) replacement requirement)		6.12		
24 Afforestation Required Threshold (AFT) =	15.00%	0.00		
25 Off-site WCA being provided on this property		0.00		
26 Woodland Conservation Required		17.19	acres	

SECTION III:Meeting the Requirements (Enter acres for each corresponding column)			
27 Woodland Preservation	7.15		
28 Afforestation / Reforestation	10.05	Bond amount:	$ 131,333.40
29 Natural Regeneration	0.00		
30 Landscape Credits	0.00		
31 Specimen/Historic Tree Credit (CRZ area * 2.0)	0.00		
32 Forest Enhancement Credit (Area * .25)	0.00		
33 Street Tree Credit (Planting w/ 10-year canopy coverage)	0.00		
34 Area approved for fee-in-lieu/PFA	0.00	Fee amount:	$0.00
35 Area approved for fee-in-lieu/non-PFA	0.00	Fee amount:	$0.00
36 Off-site Woodland Conservation Credits Required	0.00		
37 Off-site WCA (preservation) being provided on this property	0.00		
38 Off-site WCA (afforestation) being provided on this property	0.00		
39 Woodland Conservation Provided	17.20	acres	

39 Area of woodland not cleared	10.28	acres
40 Net tract woodland retained not part of requirements:	3.13	acres
41 100-floodplain woodland retained	0.00	acres
42 On-site woodland conservation provided	17.20	acres
43 On-site woodland retained not credited	±3.36	acres

44 Prepared by: Douglas S. Hodges — Signature — 7-21-16 — Date

GENERAL NOTES

1. Subject Site Description:
   Parcel 74, 75, 111
   L. 33962 F. 246
   14175 Brandywine Road, Brandywine, MD 20613
2. Area Statement:
   Parcel 74: 38,946 sq.ft. or 0.8941 acres
   Parcel 75: 45,333 sq.ft. or 1.0407 acres
   Parcel 111: 3,789,946 sq.ft. or 87.0052 acres
   Total: 3,874,227 sq.ft. or 88.9400 acres
3. Existing Site Use: Undeveloped
4. Proposed Use: Electric Utility Site
5. Property Zoned: I-2
6. Property located on Prince George's County Tax Map 145 Grid E-4.
7. Property located on Prince George's County Street Map 5883 Grid F-8.
8. Soils Survey per USDA Web Soil Survey.
9. Soils Type:
   64.81% : ApA = Aquasco Silt Loam
   1.02% : AuB = Aquasco — Urban Land
   33.92% : LQA = Lenni / Quindocqua
   0.25% : LsA = Leonardtown Silt Loam
10. Property located on Prince George's County 200' scale topography 218 SE 8 and 9, and 219 SE 9 and 9.
11. Property located on U.S.G.S. Map Brandywine Quadrangle
12. Electric service: SMECO
13. Telephone service: Verizon
14. Sewage disposal: Public
15. Water supply: Public
16. Existing Water / Sewer Categories: W-3, S-3
17. Vertical Datum: NGVD 29 (WSSC)
18. Horizontal Datum: NAD83/91
19. The subject site is located in Zone "C" of the Flood Insurance Program's Flood Insurance Rate Map on Communtly Panel #245208 0100 C.
20. The Non-Tidal Wetlands shown hereon was delineated by McCarthy and Associates and updated by Environmental Consulting & Technology, Inc. (ECT) in April, 2013.
21. Boundary Survey: The property configuration shown hereon is based on an ALTA/ACSM Land Title Survey prepared by Ben Dyer Associates Inc. The area of the subject property is 1.60 acres smaller than the previous TCP2. The area of the existing woodlands is 1.55 acres smaller than the previous TCP2.
22. The Topographical Information shown hereon is based on survey prepared by Landesign, Inc. in April, 2009 and updated in November, 2012 and updated March, 2016.
23. Zoning Regulations:
   a. Property Zoned: I-2
   b. Proposed Use: Undeveloped
   c. Minimum width from street: 25'
   d. Side and rear yards from residential zones: 20'
   e. Side yard from non-residential zones: 20'
   f. Rear yard from non-residential zones: None
   g. Minimum lot area: None
   h. Minimum lot frontage: None
   i. Maximum building area: None
   j. Maximum green area: 10%
24. Area Statement:
   Total Site Area: 3,874,227 sq.ft. or 88.9400 acres
   Disturbed Area: 2,734,301 sq.ft. or 62.7709 acres
   Undisturbed Area: 1,139,926 sq.ft. or 26.1691 acres
   Total New Impervious Cover: 405,600 sq.ft. or 9.3113 acres



VICINITY MAP — SCALE: 1" = 2000'

LEGEND

- EX. CONTOUR
- EX. BUILDING
- EX. STORMDRAIN
- EX. SANITARY SEWER
- EX. CURB & GUTTER
- EX. BENCHMARK
- EX. PROPERTY MARKER
- EX. 6' CHAIN LINK FENCE
- 6' CHAIN LINK FENCE
- EX. LIGHT POLE
- EX. TRAFFIC SIGNAL POLE
- EX. WATER VALVE
- EX. HOSE BIBB
- EX. STORM DRAIN MANHOLE
- EX. SEWER MANHOLE
- EX. TELECOMMUNICATION MANHOLE
- EX. ELECTRIC MANHOLE
- EX. FIRE HYDRANT
- EX. POWER POLE
- EX. SIGN
- EX. SIGNAL POLE BASE
- EX. BOUNDARY
- EX. ABUTTING PROPERTY
- EX. RIP-RAP
- EX. MONITORING WELL
- EX. TREELINE
- EX. TREE
- EX. SPOTSHOT
- EX. SPLIT RAIL FENCE
- OVERHEAD POWER LINES
- PROPERTY ADDRESS / HOUSE NO.
- SOILS BOUNDARY LINE
- NON-TIDAL WETLANDS LINE
- 25' WETLANDS BUFFER
- 100 YEAR WATER SURFACE ELEVATION
- PROP. 8' CHAIN LINK FENCE W/BARB
- EX. BRUSH/SAPLING LINE
- LIMITS OF DISTURBANCE
- WOODLAND PRESERVATION
- AFFORESTATION
- WOODLAND RETAINED – NOT COUNTED
- PROP. SPLIT RAIL FENCE


BRANDYWINE ROAD – MARYLAND ROUTE #381
SHA SRC #56367
(Variable R/W Width)
NORTH
NAD 83/91
AIR FORCE ROAD
(100' R/W)
N/F PARCEL 73
UNITED STATES OF AMERICA
L.8638 F.262
ADDRESS: 14200 AIR FORCE ROAD
USE: WIND SHEAR RADAR
ZONE: I2
N/F PARCEL 275
BRANDYWINE AUTO PARTS
L.4002 F.955
ADDRESS: 14153 BRANDYWINE ROAD
USE: AUTO STORAGE/SALVAGE
ZONE: I2
N/F PARCEL 288
P.G. COUNTY RIGHT-OF-WAY DIVISION
L.4323 F.793
ADDRESS: NONE
USE: UNDEVELOPED
ZONE: I2
PARCEL 111
3,789,946 ± OR
87.0052 ACRES
N/F PARCEL 74
CONSOLIDATED RAIL CORPORATION
L.6647 F.207
ADDRESS: NONE
USE: RAILROAD SUR (NON-ACTIVE)
ZONE: I2
AFFORESTATION 1.13 ACRES
AFFORESTATION 7.78 ACRES
WOODLAND PRESERVATION 5.36 ACRES
WOODLAND PRESERVATION 0.42 ACRE
WOODLAND PRESERVATION 1.37 ACRES
AFFORESTATION 1.14 ACRES
EXISTING STORMWATER MANAGEMENT POND
BM "A" BOX CUT @ N.E.CORNER HEADWALL ELEV.=233.54'
BM "6" 60 PENNY NAIL IN 8" GUM ELEV.=229.27'
Ex. Stabilized Area (Grass / Brush)
Ex. Asphalt Rd.
Ex. Commercial Apron
Ex. Railroad Crossing Signal (Typ.)
Ex. Railroad Spur
Ex. Gravel Pond Access Road
Ex. Gravel Road
Ex. Bldg Firehouse
Ex. Sediment Control Trap
Ex. Stockpile
Ex. Woods
Ex. Grass/Brush
Ex. Rip-Rap Channel
Ex. Split Rail Fence
Ex. Overhead Wires
Ex. Utility Pole
Ex. Guy Wire
Ex. Fence
Ex. Inlet
Ex. Manhole
Ex. Water Line
Ex. Gas Line
Ex. Underground Telephone Line
Ex. Underground Electric Line
Ex. Underground Cable Line
Ex. Underground Gas Line
Ex. Underground Water Line
Ex. Underground Telephone Line
Ex. Underground Electric Line
Ex. Underground Cable Line
Ex. Underground Gas Line
Ex. Underground Water Line
PROP. 8' CLF W/BARB
PROP. 8' CLF W/SLATS
PROP. 6' CLF W/SLATS
PROP. 36" SPLIT RAIL FENCE
PROP. 6' CLF W/BARB
PROP. 6' CLF W/SLATS
PROP. 36" SPLIT RAIL FENCE
PROP. 8' CLF W/BARB
PROP. 8' CLF W/SLATS